

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180926 Call Order: 006 Proposal: T2714 District:02  
 Counties: TAYLOR  
 Road Name: SR 55 (US 19)  
 Limits: FROM DIXIE CO LINE TO MILE POST 7.800  
 Project(s): 43761815201(\*) Federal Aid No: D218047B  
 Total Roadway Length: 7.831 Miles Contract Days: 170  
 Total Bridge Length: 0.000 Miles Letting Date: 09/26/18  
 Total Proposal Length: 7.831 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days Acquis.

Proposal Budget Estimate: \$7,820,264.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, guardrail, and other incidental construction on SR 55 (US 19) from Dixie CL to Mile Post 7.800 in Taylor County.

**Call Order: 006 Proposal: T2714**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43761815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43761815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,650.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	36,040.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	170.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	6,568.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	510.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	340.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	340.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,910.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	682.240
	0107- 2-	MOWING	AC	618.500
	0110- 1- 1	CLEARING & GRUBBING (43761815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,135.000
	0120- 6-	EMBANKMENT	CY	761.000
	0160- 4-	TYPE B STABILIZATION	SY	1,669.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	3,027.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,204.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	1,721.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	11,271.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	135,238.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	51,055.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	110,240.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	35,031.600

**Call Order: 006 Proposal: T2714**

ALT	Item	Description	Unit	Quantity
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	12,007.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	127.500
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	64.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,881.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	1,269.000
	0536- 1- 11	GUARDRAIL, ROADWAY, MODIFIED THRIE BEAM	LF	1,425.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	20.000
	0536- 73-	GUARDRAIL REMOVAL	LF	4,395.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	5.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	12.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	6.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	67,349.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	36.610
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	866.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	376.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	31.334
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.422
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	348.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	29.466
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	276.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.288
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43761815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	26.305
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	11.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	9.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	36.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43761815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	433.000

**Call Order: 006 Proposal: T2714**

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	188.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.211
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	174.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	138.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.144
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	18.305
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	15.667
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	14.714
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.343
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.680
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	300.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.512
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.456
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.512
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.456