

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT180926	Call Order: 008	Proposal: T2726	District:02
Counties:	DUVAL			
Road Name:	CR 115 (CHAFFEE RD)			
Limits:	AT SR 228 (NORMANDY BLVD)			
Project(s):	43583715201(*)	Federal Aid No:	D218026B	
Project(s):	43583715601	Federal Aid No:	N/A	
Total Roadway Length:	0.531 Miles	Contract Days:	170	
Total Bridge Length:	0.000 Miles	Letting Date:	09/26/18	
Total Proposal Length:	0.531 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (Acq. time)	

Proposal Budget Estimate: \$2,073,145.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of intersection improvements including the addition of lanes, milling and resurfacing, drainage improvements, signalization improvements, basework, shoulder treatment, curb and gutters, sidewalk, utility water line and other incidental construction, and signing and marking for CR 115 (Chaffee Road) at SR 228 (Normandy Blvd) near Jacksonville in western Duval County.

**Call Order: 008 Proposal: T2726**

---

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43583715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43583715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0102- 60-	WORK ZONE SIGN	ED	9,560.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	29,380.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	680.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	414.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	736.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	170.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	170.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	680.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	680.000
	0104- 10- 3	SEDIMENT BARRIER	LF	374.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	32.800
	0107- 2-	MOWING	AC	25.350
	0110- 1- 1	CLEARING & GRUBBING (43583715201)	LS	1.000

**Call Order: 008 Proposal: T2726**

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	4,100.000
	0120- 6-	EMBANKMENT	CY	1,032.000
	0160- 4-	TYPE B STABILIZATION	SY	7,773.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,724.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	4,167.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT	TN	58.200
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	5,473.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	938.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	7,156.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	446.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,408.800
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	304.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,024.500
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	82.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	16.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	3.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	81.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	46.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	17.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11,483.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.482
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.404
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	763.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	160.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.074
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.097
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	36.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.099
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	225.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.072
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	9.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000

**Call Order: 008 Proposal: T2726**

ALT	Item	Description	Unit	Quantity
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	2.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	24.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43583715201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	763.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	160.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.097
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	31.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	24.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	225.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.072
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	6.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.475
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.190
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.089
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.007
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.214
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.099
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,208.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	430.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	0634- 5- 1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	54.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	18.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	24.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	24.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	1.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-POLE 30' AND GREATER	EA	2.000
	0649- 1- 17	STEEL STRAIN POLE, F&I, TYPE PS- X	EA	2.000

**Call Order: 008 Proposal: T2726**

ALT	Item	Description	Unit	Quantity
	0649- 1-101	STEEL STRAIN POLE, FURNISH & INSTALL, CUSTOM TYPE, PROJECT 435837-1-52-01	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	4.000
	0650- 1- 17	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 2-4 WAYS	AS	2.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	5.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	8.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
<b>Section 0004 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43583715601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (43583715601)	LS	1.000