

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180926 Call Order: 002 Proposal: T3702 District:03  
 Counties: BAY  
 Road Name: SR 388  
 Limits: FROM SR 79 TO E OF NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT  
 Project(s): 42446455201(\*) Federal Aid No: D317035B  
 Project(s): 42446455601 Federal Aid No: N/A  
 Total Roadway Length: 3.949 Miles Contract Days: 1350  
 Total Bridge Length: 0.136 Miles Letting Date: 09/26/18  
 Total Proposal Length: 4.085 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Calendar Days  
 Proposal Budget Estimate: \$52,616,582.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of construction of SR 388 including adding lanes, milling and resurfacing, earthwork, base work, drainage work and existing utility removal. This project includes signing and pavement markings, signalization, lighting and landscape. The project also includes construction of new bridge numbers 460145 and 460146 which includes substructure, superstructure, test piles, approach slabs, riprap and bedding stone.

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	236.600
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	2,084.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	219.500
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	325.000
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	6,436.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	57.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	606,918.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	89,483.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	44,996.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	1,794.000
	0450- 2- 72	PREST BEAMS: FLORIDA-I BEAM 72"	LF	5,389.000
	0455- 34- 6	PRESTRESSED CONCRETE PILING, 30" SQ	LF	9,870.000
	0455-143- 6	TEST PILES-PRESTRESSED CONCRETE,30" SQ	LF	1,865.000
	0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	LF	303.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	684.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	1,558.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	3,120.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,558.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	85.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,753.700
	0530- 74-	BEDDING STONE	TN	980.700
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED- RAILINGS	LF	14,034.000

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	72.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (42446455201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42446455201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (42446455201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (42446455201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (42446455201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (42446455201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (42446455201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (42446455201)	LS	1.000
	0102- 2- 7	SPECIAL DETOUR 7 (42446455201)	LS	1.000
	0102- 2- 8	SPECIAL DETOUR 8 (42446455201)	LS	1.000
	0102- 2- 9	SPECIAL DETOUR 9 (42446455201)	LS	1.000
	0102- 2- 10	SPECIAL DETOUR 10 (42446455201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	87,110.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	6,463.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	5,013.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	328,420.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	44,800.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,801.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,753.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	17.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,104.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	4,719.000
	0104- 10- 3	SEDIMENT BARRIER	LF	90,867.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	634.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	13,694.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	12.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	293.000
	0107- 1-	LITTER REMOVAL	AC	9,235.630
	0107- 2-	MOWING	AC	5,449.310
	0110- 1- 1	CLEARING & GRUBBING (42446455201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	265.000
	0120- 1-	REGULAR EXCAVATION	CY	485,330.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	464.000
	0120- 4-	SUBSOIL EXCAVATION	CY	10,024.000
	0120- 6-	EMBANKMENT	CY	827,527.300
	0120- 74-	SURCHARGE EMBANKMENT	CY	133,092.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	31.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	40,800.000
	0160- 4-	TYPE B STABILIZATION	SY	277,454.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	471,888.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	34,794.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	11,147.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	196,713.000

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	18,391.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	12,084.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,252.200
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,295.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	36,183.800
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	6,886.800
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	1,439.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,932.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	74.600
	0350- 30- 13	CONCRETE PAVEMENT FOR ROUNDABOUT APRON, 12" DEPTH	SY	395.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	152.500
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	9.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	3.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	44.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	17.000
	0425- 1-522	INLETS, DT BOT, TYPE C, >10'	EA	1.000
	0425- 1-523	INLETS, DT BOT, TYPE C, JBOT, <10'	EA	110.000
	0425- 1-524	INLETS, DT BOT, TYPE C, JBOT, >10'	EA	52.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	15.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	6.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	4.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	8.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	5.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	15.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	19.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	7.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	17.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	220.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	132.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	404.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	15,927.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	11,617.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	9,602.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	11,762.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	2,972.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	4,112.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	408.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	302.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	139.000

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	820.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/C	LF	193.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	3.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	3.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	5.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	6.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	12.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	8.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	24.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	71.000
	0440- 1- 30	UNDERDRAIN, TYPE III	LF	1,533.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	219.000
	0442- 70-	VERTICAL DRAINAGE WICKS	LF	1,550,000.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	304.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	30,892.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	318.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	386.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	4,531.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,001.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	474.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,204.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	54.000
	0527- 2-	DETECTABLE WARNINGS	SF	437.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	26,061.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,005.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	388.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	67.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	362.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	2.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	16,236.000
	0550- 60-235	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 20.1-24' OPENING	EA	8.000
	0570- 1- 1	PERFORMANCE TURF	SY	355,899.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	130,236.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	659.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.778

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.288
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	50.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	23.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	82.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.176
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.071
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,314.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	20.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42446455201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	103.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	22.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	8.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	17.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	3.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	3.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	2.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	2.000
	0700- 11-262	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	EA	4.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	6.142
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	5.220
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	18.000
	0705- 10- 4	OBJECT MARKER, TYPE 4	EA	11.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	29.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42446455201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,500.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	189.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.404
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	73.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	82.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	374.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.172
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	731.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	505.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	36.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	36.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	13.348
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	2.448
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.922
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.654
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.591
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.296
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.296
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.296
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,606.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	990.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	49.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	3.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	3.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	33.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715- 7- 12	LOAD CENTER, F&I, PRIMARY VOLTAGE	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	33.000
<b>Section 0005 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	13,329.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,650.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	1,010.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	19,895.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	19.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	25.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	5.000

**Call Order: 002 Proposal: T3702**

ALT	Item	Description	Unit	Quantity
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 1-111	LOOP DETECTOR INDUCTIVE, F&I, TYPE 11, 4 CH, SS, RM	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0663- 1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	3.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0680- 1-112	SYSTEM CONTROL EQUIPMENT, FURNISH & INSTALL, ADAPTIVE SIGNAL CONTROL SYSTEM- NEMA, CABINET EQUIPMENT	EA	1.000
	0680- 1-113	SYSTEM CONTROL EQUIPMENT, FURNISH & INSTALL, ADAPTIVE SIGNAL CONTROL SYSTEM- NEMA, ABOVE GROUND EQUIPMENT	EA	3.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
<b>Section 0006 Landscape / Peripheral</b>				
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	718.000
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (42446455201)	LS	1.000
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (42446455201)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (42446455201)	LS	1.000
<b>Section 0007 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42446455601)	LS	1.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	5,200.000