

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180926 Call Order: 015 Proposal: T6458 District:06  
 Counties: MIAMI-DADE  
 Road Name: SR 5 (US 1)  
 Limits: FROM LEJEUNE RD TO SE 4TH ST AND FROM NE 22 ST TO SANS SOUCI BLVD  
 Project(s): 44018915201 Federal Aid No: D618040B  
 Project(s): 44019115201(\*) Federal Aid No: D618038B  
 Total Roadway Length: 12.252 Miles Contract Days: 200  
 Total Bridge Length: 0.000 Miles Letting Date: 09/26/18  
 Total Proposal Length: 12.252 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 100 Calendar Days  
 Proposal Budget Estimate: \$1,433,346.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of signalized intersection lighting along SR 5 ( US 1).

**Call Order: 015 Proposal: T6458**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44018915201)	LS	1.000
	0101- 1-	MOBILIZATION (44019115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44018915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44019115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,190.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,530.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	920.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	6,892.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	460.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	516.000
	0110- 1- 1	CLEARING & GRUBBING (44019115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	651.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44018915201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44019115201)	LS	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	658.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44018915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44019115201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,427.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	134.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	28,811.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	335.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	14,890.000

**Call Order: 015 Proposal: T6458**

ALT	Item	Description	Unit	Quantity
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	15.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	52.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	17.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	26.000
	0715- 21- 2	LIGHTING REPAIRS AND RETROFITS, LED RETROFIT KIT FOR EXISTING LUMINAIRE	EA	74.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	95.000
	0715-511-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	12.000
	0715-511-740	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, STAINLESS STEEL, 40'	EA	3.000
	0715-516-115	LIGHT POLE COMPLETE-SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, 15'	EA	8.000
	0715-516-125	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT- ALUMINUM, 25'	EA	3.000
<b>Section 0003 Landscape / Peripheral</b>				
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.110
	0580- 2- 2	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK	EA	5.000