

**BID SOLICITATION NOTICE**  
**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**CONSTRUCTION AND MAINTENANCE PROGRAMS**  
605 Suwanee St., MS-55, Tallahassee FL 32399

Tallahassee, FL  
April 20, 2018  
Advertisement No. 2

All bids must be completed using **Project Bids** software available on the Bid Express website at <https://bidx.com/fl/main>

Unless otherwise stipulated in the proposal description, bids for all projects listed in this Bid Solicitation Notice must be submitted using Bid Express only. No other means of submission of bids will be accepted. Please visit the Contracts Administration Website at: <http://www.fdot.gov/contracts> for more information on Bid Express. Submitting bids through Bid Express requires a Digital ID. To obtain a Digital ID, please contact Bid Express at <http://www.bidx.com>. Allow up to 6 days to complete the Digital ID registration.

Bids for the projects in this Bid Solicitation Notice will be accepted by Bid Express until 10:30 A.M. (Eastern Time) on **Wednesday, May 23, 2018**.

Bid totals for each bid submitted will be read aloud for those present and will be available at 11:15 A.M., May 23, 2018 in the Contracts Administration Office, Tallahassee, Florida or on the Contracts Administration Website at: <http://www.fdot.gov/contracts>. Agenda: a) Opening Remarks; b) 15 minutes of public input; c) Reading of bids; d) Closing. Anyone needing special accommodations under the Americans with Disabilities Act of 1990 should send an e-mail to: [contracts.admin@dot.state.fl.us](mailto:contracts.admin@dot.state.fl.us) or call telephone number (850)414-4000. Special accommodation requests under the Americans with Disabilities Act should be made at least seven days prior to the public meeting. Bidders may obtain preliminary bid results at: <https://fdotwp1.dot.state.fl.us/wTBidLetting/LettingMain>, select Central Office then click on appropriate date.

**DEADLINE FOR PROPOSALS AND PROPOSAL HOLDERS LIST**

The deadline for obtaining bid packages shall be 24 hours prior to the scheduled letting date and time. A list of plan holders may be obtained by visiting the Contracts Administration website at: <http://www.fdot.gov/contracts>, click "Letting and Project Information" and select letting date from the Lettings Menu. For compliance with Florida Statute 337.168(2), additional bidders and plan and specifications holders are not published beginning three working days prior to the letting.

**-----NOTE-----**

**Proposals will not be issued after 10:30 A.M. (Eastern Time) on Tuesday, May 22, 2018 .**

**Document Ordering Information**

Orders for documents are placed using the Contract Proposal Processing Online Ordering System at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/>. There is no charge for ordering/downloading documents. Online Ordering is available Monday through Friday from 6 AM. to 9 PM. and Saturday from 6 AM. to 7 PM.

**To Place An Order**

- A current State of Florida Vendor Number is required prior to first-time registration; please visit [http://dms.myflorida.com/egovernment\\_tools/myflorida\\_marketplace](http://dms.myflorida.com/egovernment_tools/myflorida_marketplace) for more information. Please allow 24 hours for receipt of a new vendor number.
- Prior to placing orders, an individual shall register and establish an Internet Subscriber Account with the department of Transportation at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/>. Please allow 48 to 72 hours (excluding weekends and holidays) for the registration and approval.

**PREQUALIFICATION**

Contractors must have a current certificate of qualification in accordance with Florida Statute 337.14(1) and Rule Chapter 14-22, Florida Administrative Code, on the date of the letting to bid on construction projects over \$250,000.00 as established by the Department's budget.

## **PREQUALIFIED CONTRACTORS CURRENT CAPACITY**

In order for the Department to have the information required to determine a prequalified bidder's Current Capacity, it is necessary that the prequalified contractor certify the total dollar amount of all work the contractor has underway. This certification shall be accomplished electronically by submitting the Certification of Work Underway (Online Web Application) [http://www.fdot.gov/contracts/PreQual\\_Info/prequalified.shtm](http://www.fdot.gov/contracts/PreQual_Info/prequalified.shtm) to the Department every 30 calendar days.

## **CONFLICT OF INTEREST**

A contractor who performs a constructability review on a design contract or who participates in a value engineering study workshop or cost risk analysis workshop, is prohibited from bidding on the construction of that contract.

## **SCRUTINIZED COMPANIES**

A company that is on the Scrutinized Companies that Boycott Israel List, is engaged in a boycott of Israel, is on the Scrutinized Companies with Activities in Sudan List, is on the Scrutinized Companies with Activities in the Iran Petroleum Energy Sector List, may not bid on, submit a proposal for, or enter into a contract with an agency or local government entity for goods or services of \$1 million or more.

## **BID REJECTION**

Bidders are hereby notified that all bids on any of the following projects are likely to be rejected if the lowest responsive bid received exceeds the engineer's estimate by more than ten percent (10%). In the event any of the bids are rejected for this reason, the project may be deferred for re-advertising. In addition, award of all federally funded projects will be subject to Federal Highway Administration concurrence.

## **PROTEST RIGHTS**

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid solicitation** shall file both a notice of protest and bond within 72 hours after posting of the Bid Solicitation Notice, and shall file a formal written protest within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid solicitation pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid solicitation that requires qualification of bidders, the bond shall be \$5,000. For an action protesting a bid solicitation for which bidders are not required to be prequalified by the Department to be eligible to bid, the bond shall be \$2,500. The required notice of protest, bond and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street, Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), F.S., or failure to post the bond or other security required by law within the time allowed for the filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid rejection or contract award** shall file both a notice of protest and bond within 72 hours after the posting of the Summary of Bids. If notice of intended decision is given by certified mail or express delivery, the adversely affected person must file both the notice of protest and bond within 72 hours after receipt of the notice of intent. A formal written protest must be filed within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid rejection or contract award pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid rejection or contract award that requires qualification of bidders, the Bond shall be equal to one percent of the lowest bid submitted or \$5,000, whichever is greater. For an action protesting a bid rejection or contract award for which bidders are not required to be prequalified by the Department to be eligible to bid, the bond shall be \$2,500. The required notice of protest, bond, and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street, Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), Florida Statutes, shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

A protest is not timely filed unless the notice of protest, bond, and the formal protest are each received by the Clerk of Agency Proceedings within the required time limits. A protest which is filed prematurely will be deemed abandoned unless timely renewed.

Interested parties can visit our Internet web site at <http://www.fdot.gov/contracts/>. Information regarding projects posted with the Clerk of Agency Proceedings, Proposal holders, Plan and Special Provisions holders, preliminary letting results,

and other noteworthy information is provided on this website. Please note that, for compliance with Florida Statute 337.168(2), the Proposal holder and the Plan and Special Provision holder listings are not published beginning three working days prior to the letting until after the letting.

In the event multiple responsive bidders submit identical proposals (bids), the Department will determine the order in which proposals are to be considered for Contract award in accordance with Florida Laws, and any applicable Rules.

### **INSURANCE**

The successful bidder shall submit current general liability insurance and workman's compensation insurance certificates for the duration of the contract in the dollar amounts and manner specified in the most current edition of the Department's Standard Specifications for Road and Bridge Construction. Insurance companies must be authorized to do business in the State of Florida. Proof of such insurance shall be filed with the District Contracts and Procurement Office before the contract can be executed. BE SURE THAT THE CONTRACT NUMBER IS ON EACH INSURANCE CERTIFICATE.

### **ADDENDA**

No negotiations, decisions, or actions will be initiated or executed by a potential bidder as a result of any oral discussion with a State employee. Only those communications which are in writing from the Department will be considered as a duly authorized expression on behalf of the Department. Notices of changes (addenda) will be posted on the Contracts Administration website at: <http://www.fdot.gov/contracts/>, click "Letting and Project Information" and select letting date from the Lettings Menu. It is the responsibility of all potential bidders to monitor this site for any changing information prior to submitting their bid. **All addenda shall be acknowledged when submitting Bids.**

### **BID QUESTIONS**

All work is to be done in accordance with the Plans, Specifications, and Special Provisions of the State of Florida Department of Transportation. Direct questions regarding the advertised projects by posting them to the Department website at the following URL address:

<https://fdotwp1.dot.state.fl.us/BidQuestionsAndAnswers/Proposal.aspx/SearchProposal>.

### **PROPOSAL GUARANTY**

For bids over \$150,000.00, the standard proposal guaranty of 5% of the bid will be required, unless otherwise stipulated in the proposal advertisement. A Proposal Guaranty of not less than five percent (5%) of the total actual bid in the form of either a certified check, cashier's check, trust company treasurer's check, bank draft of any national or state bank, or a Surety Proposal Guaranty made payable to the Florida Department of Transportation must be received for each bid in excess of **\$150,000.00**. A check or draft in an amount less than five percent (5%) of the actual bid will invalidate the bid. The guaranty amount shall include all bid items except construction days for A+B bidding and lane closure for Lane Rental Bidding. Proposal Guaranty shall substantially conform to DOT Form 375-020-09 furnished with the Proposal. Surety2000 or SurePath electronic Proposal Guaranty submittal may be used in conjunction with Bid Express internet bid submittal. For more information please visit <http://www.surety2000.com> for Surety2000 or <http://www.insurevision.com> for SurePath. Paper Proposal Guaranty will also be accepted for bids submitted through Bid Express provided they are received prior to the deadline for receiving bids, by the location(s) identified in this Bid Solicitation Notice. If an electronic proposal guaranty is not being submitted, the bidder must submit an original proposal guaranty. (A fax or a copy sent as an attachment will not be accepted.)

### **EXECUTION OF CONTRACT**

Pursuant to Subsections 3-6 and 3-7 of the Standard Specifications, the successful bidder shall execute the necessary contract documents and return the agreement along with a satisfactory Performance and Payment Bond within ten (10) Calendar days of award, excluding Saturdays, Sundays, and state holidays, unless noted otherwise in the project specifications. A 100% Payment and Performance Bond will be required for all projects unless noted otherwise in the project specifications. All work is to be done in accordance with the Plans, special Provisions of the State of Florida Department of Transportation.

Prior to execution of the contract with the Department, **a corporation must show proof that it is authorized to do business in the State of Florida.** Florida corporations should provide a copy of the certificate of Incorporation and foreign corporations should provide a copy of Certificate of Authority from the Florida Department of State.

**Important Note:** Actual commitment and final execution of the contract is contingent upon an approved legislative budget and funds availability.

### **DBE PARTICIPATION.**

Disadvantaged Business Enterprise (DBE) Availability Goal Information is contained in the Bid Solicitation Package. DBE Participation and Bidder Opportunity List for Prime Contractors should be reported in the **Equal Opportunity Compliance (EOC)** system. The EOC system is a web based application for Prime Contractors, statewide, to report their Bidder Opportunity List, DBE Commitments, and DBE/MBE Subpayments. Please complete and submit the DBE Participation (i.e. DBE Commitments) and Bid Opportunity List in the EOC.

More information regarding EOC can be referenced at: <http://www.fdot.gov/equalopportunity/eoc.shtm>

### **DEBARMENT/SUSPENSION**

All bids submitted to the Department shall include a statement that by signing and submitting this proposal, the bidder certifies that no principal (which includes officers, directors or executives) is presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from participation in this transaction by any federal department or agency.

### **MANDATORY PRE-BID CONFERENCE**

For projects with mandatory Pre-Bid Meeting, proposals (BIDDING DOCUMENTS) will be issued only to the attendees of the meeting. Prospective bidders ordering bidding documents prior to the Pre-Bid Meeting will be given access to download the bidding documents within 24 hours after the Pre-Bid Meeting. Those prospective bidders ordering the documents after the Pre-Bid Meeting will need to contact the office advertising the project to confirm attendance and receive access to download the bidding documents. Please contact the office at least two working days prior to the deadline for obtaining bidding documents to allow time for processing.

### **LATE ARRIVALS TO MANDATORY PRE-BID MEETINGS**

All bidders must be present and signed in prior to the start of the mandatory Pre-Bid Meeting. Anyone not signed in at the commencement of the meeting will be considered late and will not be allowed to bid on the project.

### **FIRST TIME BIDDERS**

Bidders bidding for the first time with the Department can access the New Bidder's Orientation document at: [http://www.fdot.gov/contracts/Cpp\\_Online\\_Ordering/NEW%20BIDDERS%20ORIENTATION.pdf](http://www.fdot.gov/contracts/Cpp_Online_Ordering/NEW%20BIDDERS%20ORIENTATION.pdf)

### **POSTING NOTICE**

The bid tabulation and intent to award will be posted on **June 06, 2018** or **June 20, 2018** at <http://www.fdot.gov/contracts/>, click the "[Letting and Project Information](#)" and select letting date from the Listings Menu. The posting provides notice of the Department's intent to award a contract or reject all bids. The Department's Notice of Intent regarding a project will be posted on only one of the alternate posting dates. Bidders are solely responsible for timely monitoring or otherwise verifying on which of the specified alternate posting dates the posting of award or rejection of all bids actually occurs.

If the posting dates are revised, all bidders for the subject project will be notified.

### **AFFIRMATIVE ACTION (EQUAL EMPLOYMENT OPPORTUNITY)**

The Florida Department of Transportation (hereinafter referred to as the "Department"), in accordance with **Title VI of the Civil Rights Act of 1964, 42 USC 2000d to 2000d-4 and related authorities, Title 49, Code of Federal Regulations, U.S. Department of Transportation, Subtitle A, Office of the Secretary, Part 21**, Nondiscrimination in Federally-assisted programs of the U.S. Department of Transportation issued pursuant to such Act, hereby notifies all bidders that the Department will affirmatively insure that in any contract entered into pursuant to this advertisement, minority and disadvantaged business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the basis of race, color, national origin, or sex in consideration for an award. Further, it is the policy of the Department to not discriminate against bidders on the grounds of race, color, national origin, religion, sex, age, or disability/handicap in consideration for an award. A bidder must have an approved DBE Affirmative Action (DBE/AA) Plan prior to contract award. Please use the following link [http://www.fdot.gov/contracts/cpp\\_online\\_ordering/bidder\\_assist.shtm](http://www.fdot.gov/contracts/cpp_online_ordering/bidder_assist.shtm), the Standard Specifications for Road and Bridge Construction and the Special Provisions for instructions for submission of a DBE/AA Plan. The DBE/AA Plan should be submitted for approval prior to the bidding.

### **MINIMUM WAGE**

The minimum wage for all hours worked in Florida is available at <http://www.floridajobs.org>.

### **EMAIL SUBSCRIPTION LIST**

To get on the e-mail subscription list, go to <http://www2.dot.state.fl.us/ContractsAdministration/bsnmail.asp> and fill out the necessary information to "Subscribe". To obtain information concerning other districts, go to <http://www.fdot.gov/contracts/distco.shtm>.

### **NOTICE TO ALL BIDDERS**

To report bid rigging activities call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

By submitting a bid, the contractor/consultant/vendor agrees to comply with section 20.055(5).Florida Statute, and to incorporate in all subcontracts the obligation to comply with section 20.055(5) Florida Statute.

**Florida Department of Transportation  
Notice to Contractors Index**

Published: April 20, 2018

Letting ID: CT180523

Please use the following proposal ID and the letting ID when ordering plans/proposal or specifications for the May 23, 2018 letting.

Page Number	Proposal Id	Proposal Notes	Fin Proj Numbers	County
7	T1705		44012615201 44013315201(*) 44013715201	MANATEE, SARASOTA
9	T1713	LS	43355215201(*)	SARASOTA
10	T2692	SS	43817115201 43952415201(*)	DUVAL
14	T2702		43616515201(*)	TAYLOR
17	T2703		21272425201(*)	DIST/ST-WIDE, LAFAYETTE, SUWANNEE
21	T3669		43046415201(*)	BAY
23	T4478		43206645201(*) 43206645202 43206645203	BROWARD
28	T4482		44007915201(*) 44008015201	PALM BEACH
30	T4483		44008115201(*) 44008115202 44008215201 44008315201 44008415201 44008515201	BROWARD
33	T4484		43169815201(*) 43169815202	BROWARD
36	T4485		43634115201(*) 43634115202	BROWARD
39	T6438	I/D	43117015201(*) 43117015202 43117015601 43117025201 43117055201 43117055202	MIAMI-DADE
45	T7409		43649115201 43649115202(*)	HILLSBOROUGH
48	T7410		43649515201(*) 43649515202 43649515203 43649515204 43649515601	HILLSBOROUGH

**Proposal Note Codes:**

LS: Lump Sum Bidding    SS: Special Start Date    I/D: Incentive/Disincentive Bidding

*Note: (\*) indicates lead project*

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: CT180523 Call Order: 008 Proposal: T1705 District:01  
Counties: MANATEE, SARASOTA  
Road Name: SR 45 AND SR 780  
Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS  
Project(s): 44012615201 Federal Aid No: D117093B  
Project(s): 44013315201(\*) Federal Aid No: D117095B  
Project(s): 44013715201 Federal Aid No: D117097B  
Total Roadway Length: 4.672 Miles Contract Days: 110  
Total Bridge Length: 0.000 Miles Letting Date: 05/23/18  
Total Proposal Length: 4.672 Miles Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 90 Days (Aqui Time)  
Proposal Budget Estimate: \$531,676.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of highway lighting and sidewalk SR 45 at the intersections of 30th Ave W., 21st Ave W., 17th Ave. W., 12th Ave. W., 9th Ave. W., 23rd St E., 17th St. E., 13th Ave. E., and 9th Ave E. in Manatee County and along SR 780 at the intersection of East Ave. in Sarasota County.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 008 Proposal: T1705**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44012615201)	LS	1.000
	0101- 1-	MOBILIZATION (44013315201)	LS	1.000
	0101- 1-	MOBILIZATION (44013715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,806.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,131.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	485.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	62.000
	0104- 10- 3	SEDIMENT BARRIER	LF	37.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	21.000
	0107- 1-	LITTER REMOVAL	AC	1.130
	0107- 2-	MOWING	AC	0.360
	0110- 1- 1	CLEARING & GRUBBING (44012615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	134.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	120.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013715201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	379.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,715.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	10,858.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	936.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	18.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	5.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	3.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	20.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	28.000

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180523      Call Order: 009      Proposal: T1713      District:01

Counties: SARASOTA

Road Name: SR 45 (US 41) (TAMIAMI TRAIL)

Limits: FROM TUSCOLA BLVD TO ORTIZ BLVD

Project(s): 43355215201(\*)      Federal Aid No: D118038B

Total Roadway Length:	2.134 Miles	Contract Days:	230
Total Bridge Length:	0.000 Miles	Letting Date:	05/23/18
Total Proposal Length:	2.134 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days (Aqui Time)

Proposal Budget Estimate: \$2,435,757.00

Please read the full advertisement

Description: Lump Sum

The improvements under this contract consist of constructing multi-use path, bus and shelter pads, sidewalks, drainage improvements, guardrail, lighting, signing and pavement marking and signalization on State Road 45 (U.S. 41) (Tamiami Trail) from Tuscola Boulevard westerly approximately 2.134 miles, to Ortiz Boulevard, in the City of North Port, Sarasota County.

**Call Order: 009 Proposal: T1713**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0999- 2-	LUMP SUM CONTRACT, ALTERNATIVE BIDDING (43355215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43355215201)	LS	1.000



**Call Order: 010 Proposal: T2692**

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	480.000
	0107- 1-	LITTER REMOVAL	AC	3,923.280
	0107- 2-	MOWING	AC	3,475.420
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	5,279.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	211.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	145.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43817115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43952415201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	7.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	7.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	4.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	2.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	3.000
	0700- 3-210	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 501-600 SF	EA	6.000
	0700- 3-506	SIGN PANEL, RELOCATE, 101-200 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 3-608	SIGN PANEL, REMOVE, 301-400 SF	EA	11.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	1.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	1.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	2.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	3.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43952415201)	LS	1.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	16.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	28.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	15.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.181
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.544
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.181
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	11.894
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	12.664
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	6.136

**Call Order: 010 Proposal: T2692**

ALT	Item	Description	Unit	Quantity
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	12.664
<b>Section 0004 Intelligent Transportation System</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	10,372.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,189.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	35,837.000
	0633- 1-111	FIBER OPTIC CABLE, F&I, OVERHEAD,2-12 FIBERS	LF	6,974.000
	0633- 1-112	FIBER OPTIC CABLE, F&I, OVERHEAD,13-48 FIBERS	LF	32,807.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	8,194.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	81.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	108.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	21.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	21.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	84.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	21.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	977.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	29.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	18.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	112.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	42,281.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	18.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	5.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	21.000
	0639- 6- 2	ELECTRICAL POWER SERVICE- TRANSFORMER, REPLACE EXISTING	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	6.000
	0649- 2-150	STEEL CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 50'	EA	15.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	13.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	13.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	17.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	4.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	21.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	21.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	21.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	13.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	21.000

**Call Order: 010 Proposal: T2692**

ALT	Item	Description	Unit	Quantity
	0700- 7-132	EMBEDDED DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, FULL COLOR, 12-20 SF	EA	13.000
	0700- 8-134	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, FULL COLOR, 31-50 SF	EA	52.000
	0700- 8-136	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- W/UPS, FULL COLOR, 101-200 SF	EA	13.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	2.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 10-115	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	13.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000



**Call Order: 011 Proposal: T2702**

ALT	Item	Description	Unit	Quantity
	0425- 1-441	INLETS, CURB, TYPE J-4, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	11.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	9.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	556.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/CD	LF	1,026.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	LF	1,770.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	16.700
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	363.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	2,636.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	364.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	145.000
	0527- 2-	DETECTABLE WARNINGS	SF	276.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,755.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.758
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.114
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,612.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	72.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	606.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	10.024
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.790
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	58.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.354
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	40.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	3.590
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43616515201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	28.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43616515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	806.000

**Call Order: 011 Proposal: T2702**

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	36.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	303.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.395
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	29.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	20.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.795
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	405.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	37.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	37.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.879
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.057
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.012
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.177
<b>Section 0003 Signalization</b>				
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	6.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	8.000



**Call Order: 012 Proposal: T2703**

ALT	Item	Description	Unit	Quantity
	0450- 2- 84	PREST BEAMS: FLORIDA-I BEAM 84"	LF	2,514.000
	0455- 88- 5	DRILLED SHAFT, 48" DIA	LF	572.000
	0455- 88- 7	DRILLED SHAFT, 72" DIA	LF	658.000
	0455-103-135	LOAD TEST - STATNOMIC, COMPRESSION, 3500TN	EA	2.000
	0455-107- 5	DRILLED SHAFT CASING, 48" DIAMETER	LF	303.000
	0455-107- 7	DRILLED SHAFT CASING, 72" DIAMETER	LF	174.000
	0455-111-	CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION	LF	754.000
	0455-122- 5	EXCAVATION UNCLASSIFIED SHAFT, 48" DIA	LF	567.000
	0455-122- 7	EXCAVATION UNCLASSIFIED SHAFT, 72" DIA	LF	474.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	5,479.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	12,399.000
	0455-142-	CROSSHOLE SONIC LOGGING	EA	22.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	93.000
	0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	LF	47.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,630.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	59.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,778.700
	0530- 74-	BEDDING STONE	TN	990.100
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	4,319.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	773.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (21272425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21272425201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	25.000
	0102- 60-	WORK ZONE SIGN	ED	11,368.000
	0102- 71- 11	TEMPORARY BARRIER, F&I, CONCRETE	LF	900.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,138.000
	0102- 71- 21	TEMPORARY BARRIER, RELOCATE, CONCRETE	LF	663.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	47,870.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,584.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	286.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,100.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	550.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	1,630.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	2,445.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,882.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,043.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	889.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000

**Call Order: 012 Proposal: T2703**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (21272425201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (21272425201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (21272425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	5.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (21272425201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	17,339.000
	0120- 4-	SUBSOIL EXCAVATION	CY	20.000
	0120- 6-	EMBANKMENT	CY	32,105.000
	0160- 4-	TYPE B STABILIZATION	SY	11,494.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,726.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	6,599.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	2,004.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	928.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	960.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	69.600
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	13.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	9.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	76.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	91.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	569.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	39.000
	0430-611-225	U-ENDWALL WITH BAFFLES, STD 261, 1:3 SLOPE, 18"PIPE	EA	2.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	19.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	844.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	19.400
	0530- 74-	BEDDING STONE	TN	13.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,557.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	7.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,968.000
	0536- 85- 22	GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL	EA	2.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	3.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0550- 10-120	FENCING, TYPE A, 5.1-6.0, STANDARD	LF	473.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	35,002.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.840
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.243
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21272425201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000

**Call Order: 012 Proposal: T2703**

ALT	Item	Description	Unit	Quantity
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	13.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21272425201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	32.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.096
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.070
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.007
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.890
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.309
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.309



**Call Order: 013 Proposal: T3669**

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	2,030.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	580.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,650.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	235.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43046415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43046415201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,241.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	220.300
	0120- 5-	CHANNEL EXCAVATION	CY	220.000
	0160- 4-	TYPE B STABILIZATION	SY	6,356.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	969.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	82.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	5,796.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	475.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	945.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	653.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	87.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	16.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,469.000
<b>Section 0003 Signing</b>				
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43046415201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.091
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.091
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024



**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43206645201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43206645201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43206645201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	6,865.000
	0120- 1-	REGULAR EXCAVATION	CY	2,688.000
	0120- 6-	EMBANKMENT	CY	60.000
	0160- 4-	TYPE B STABILIZATION	SY	4,745.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	54.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,745.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	58,221.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	369.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	3,311.600
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	9.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	6.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	29.000
	0425- 6-	VALVE BOXES, ADJUST	EA	26.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	1,497.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	20.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	20.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	12.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	6,858.000
	0520- 1- 11	CONCRETE CURB & GUTTER, VARIABLE HEIGHT TYPE F	LF	12.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	190.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	90.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	64.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	566.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,310.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,667.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	60.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	1,286.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	117.000
	0527- 2-	DETECTABLE WARNINGS	SF	534.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,755.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.581
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.387
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,198.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	619.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.111
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.309
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	76.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.891
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	21.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.089
	0751- 35- 13	ARCHITECTURAL, BUS SHELTER, F&I, 101-150 SF	EA	1.000
	0751- 35- 43	ARCHITECTURAL, BUS SHELTER, RELOCATE, 101-150 SF	EA	2.000
	0751- 36- 12	BICYCLE RACK, FURNISH & INSTALL, 2-6 BICYCLES	EA	4.000
	0751- 37-	TRASH RECEPTACLE	EA	4.000
	0999- 16-	PARTNERING, DO NOT BID (43206645201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645203)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	22.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	12.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	511.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43206645201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,198.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	619.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.309
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	76.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	21.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.089
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,750.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	43.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	43.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.601
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.387
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.111
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.891
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	892.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,647.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	9,537.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	6,966.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	12.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	7.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	14.000
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,185.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	840.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	39.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-410	ELECTRICAL POWER SERVICE, REL OVERHEAD	AS	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	10.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	2.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	22.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	18.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
<b>Section 0005 Landscape / Peripheral</b>				
	0580- 2- 5	LANDSCAPE- RELOCATE TREE, TREES >5" CALIPER (43206645201)	EA	10.000
	0580- 2- 8	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK SABAL PALM ONLY (43206645201)	EA	3.000

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT180523	Call Order: 015	Proposal: T4482	District:04
Counties:	PALM BEACH			
Road Name:	SR 708 (W BLUE HERON BLVD) AND SR 809 (N MILITARY TRAIL)			
Limits:	VARIOUS INTERSECTIONS FROM SHILOH DR TO BURNS RD			
Project(s):	44007915201(*)	Federal Aid No:	D418013B	
Project(s):	44008015201	Federal Aid No:	D418014B	
Total Roadway Length:	6.483 Miles	Contract Days:	253	
Total Bridge Length:	0.047 Miles	Letting Date:	05/23/18	
Total Proposal Length:	6.483 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:	\$531,304.00			

Please read the full advertisement

Description:

The improvements under this contract consist of lighting retrofit for three intersections along SR 708 (W. Blue Heron Blvd.) and eleven intersections along SR 809 (N. Military Trail).

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 015 Proposal: T4482**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44007915201)	LS	1.000
	0101- 1-	MOBILIZATION (44008015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44007915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44008015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,175.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,978.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	777.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	253.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	253.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	205.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	148.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44007915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008015201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,645.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	41.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	14,463.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	13.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	4.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	8.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	30.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	23.000



**Call Order: 016 Proposal: T4483**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44008315201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44008415201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44008515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44008115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44008215201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44008315201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44008415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44008515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	629.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	19.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	491.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	144.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	146.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008515201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,560.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	136.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	87.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	18,810.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,943.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	16.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	11.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	2.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	64.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	21.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	85.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	42.000
	0715-511-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	12.000

**Call Order: 016 Proposal: T4483**

ALT	Item	Description	Unit	Quantity
	0715-512-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008115202)	LS	1.000

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180523	Call Order: 017	Proposal: T4484	District:04
Counties:	BROWARD			
Road Name:	PETERS RD			
Limits:	FROM PINE ISLAND RD TO SR 817 (UNIVERSITY DR)			
Project(s):	43169815201(*)	Federal Aid No:	D417061B	
Project(s):	43169815202	Federal Aid No:	D417061B	
Total Roadway Length:	0.779 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	05/23/18	
Total Proposal Length:	0.779 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:	\$1,536,151.00			

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, widening for the addition of bicycle lanes, patterned pavement in bicycle lanes, sidewalk and detectable warnings, drainage, signing and pavement markings, pedestrian signals, and lighting retrofit along Peters Rd.

**Call Order: 017 Proposal: T4484**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43169815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43169815201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	9.400
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	116.000
	0102- 60-	WORK ZONE SIGN	ED	16,329.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,013.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	51,570.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	486.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	5,740.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,200.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,164.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, SKIP	LF	2,073.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	960.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	2,073.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,863.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	26.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43169815201)	LS	1.000

**Call Order: 017 Proposal: T4484**

ALT	Item	Description	Unit	Quantity
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43169815202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43169815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,642.000
	0120- 1-	REGULAR EXCAVATION	CY	2,083.300
	0120- 6-	EMBANKMENT	CY	39.700
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	11.200
	0160- 4-	TYPE B STABILIZATION	SY	4,952.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,873.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	32,948.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	308.200
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,120.300
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	2.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	10.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	103.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	10.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	12.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,017.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	7.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	223.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	760.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	780.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	121.000
	0527- 2-	DETECTABLE WARNINGS	SF	191.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,954.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.475
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.475
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43169815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43169815202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	28.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	9.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	5.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	211.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43169815201)	LS	1.000

**Call Order: 017 Proposal: T4484**

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	918.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	699.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	342.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.066
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	71.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	68.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.220
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	15.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.370
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.065
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.321
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.079
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.380
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	15.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	165.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	12.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	2.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000



**Call Order: 018 Proposal: T4485**

ALT	Item	Description	Unit	Quantity
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	28,096.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,552.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	860.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	39.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	21.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	25.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	4.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	3.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	32.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	100.000
	0715-511-350	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, CONCRETE, 50'	EA	6.000
	0715-512-350	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, CONCRETE, 50'	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43634115202)	LS	1.000
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	494.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,840.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	4,135.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	4,864.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	2.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	34.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	19.000
	0639- 1-420	ELECTRICAL POWER SERVICE, RELOCATE, UNDERGROUND	AS	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	17.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 13	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 2 SECTION, 1-2 WAYS	AS	5.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	3.000

**Call Order: 018 Proposal: T4485**

ALT	Item	Description	Unit	Quantity
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	3.000
	0660- 6-112	VEHICLE DETECTION SYSTEM- AVI, TRANSPONDER, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	13.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	9.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	8.000
	0670- 5-122	TRAFFIC CONTROLLER ASSEMBLY, F&I,170,2 PREEMPTION PLANS	AS	3.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	3.000
	0676- 2-111	ITS CABINET, FURNISH & INSTALL, POLE MOUNT, 336, 24" W X 36" H X 20" D	EA	19.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0684- 6- 11	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET ACCESS POINT	EA	4.000
	0684- 6- 12	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT	EA	8.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	17.000
	0700- 11-222	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWERED, ELECTRONIC REGULATORY SIGN, 12-20 SF	AS	5.000
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	9.000



**Call Order: 019 Proposal: T6438**

ALT	Item	Description	Unit	Quantity
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,900.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,900.000
	0104- 10- 3	SEDIMENT BARRIER	LF	411.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	65.000
	0107- 1-	LITTER REMOVAL	AC	35.040
	0107- 2-	MOWING	AC	23.010
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43117055201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43117015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43117015202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43117025201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43117055202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,125.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43117015201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43117025201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43117055201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	928.600
	0120- 6-	EMBANKMENT	CY	157.200
	0160- 4-	TYPE B STABILIZATION	SY	446.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	648.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,535.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	45,881.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	58,900.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	14.400
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	42.700
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	91.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	8,687.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	31.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	26.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0425- 1-891	INLETS, BARRIER WALL, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	31.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	10.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	19.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,870.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	170.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	4.000
	0521- 72- 11	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 54"	LF	266.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,708.000

**Call Order: 019 Proposal: T6438**

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,173.000
	0527- 2-	DETECTABLE WARNINGS	SF	735.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	633.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	152.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	497.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	5.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	707.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	540.000
	0580- 2- 2	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK	EA	11.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	90.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	45.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 5- 1	TRAFFIC MONITORING SITE SOLAR POWER UNIT, FURNISH & INSTALL	EA	1.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	1.000
	0695- 8- 11	TRAFFIC MONITORING SITE COMMUNICATIONS MODEM FURNISH & INSTALL	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.092
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.171
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,507.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	252.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,792.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	7.883
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.177
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	44.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	70.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.289
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.039
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	136.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.285
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117015201)	LS	1.000

**Call Order: 019 Proposal: T6438**

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117015202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117025201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117055201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117055202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	51.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	6.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	47.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	20.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43117015201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43117015202)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43117025201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43117055202)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,565.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	261.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,310.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.200
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	30.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	81.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	166.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.108
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,073.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,953.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.387
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.188
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.935
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.016
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.037
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.051
<b>Section 0003 Lighting</b>				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000

**Call Order: 019 Proposal: T6438**

ALT	Item	Description	Unit	Quantity
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,028.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	2,526.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	119.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	400.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	19.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	3.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 13	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-50'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	7.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	23.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	21.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	14.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	26.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	26.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	29.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	8.000
	0670- 5-120	TRAFFIC CONTROLLER ASSEMBLY, F&I, 170	AS	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	7.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	5.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000

**Call Order: 019 Proposal: T6438**

ALT	Item	Description	Unit	Quantity
<b>Section 0005 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43117015601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	16.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	23.000



**Call Order: 020 Proposal: T7409**

ALT	Item	Description	Unit	Quantity
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43649115201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43649115202)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	96.900
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43649115201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43649115202)	LS	1.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	19,372.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,130.800
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	6.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425-100- 3	INLET SPECIAL DRAINAGE GRATE, PROJECT 436491-1-52-01	LF	37.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	144.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	16.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	41.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	302.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	84.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	1,958.000
	0520- 7- 2	GRANITE CURB, RESET	LF	304.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,234.000
	0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	33.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	186.000
	0527- 2-	DETECTABLE WARNINGS	SF	736.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	191.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	41.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649115202)	LS	1.000
<b>Section 0002 Signing</b>				
	0654- 2- 21	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR POWERED, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	8.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	18.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	10.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	31.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	44.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	44.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	79.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43649115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,954.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	765.000

**Call Order: 020 Proposal: T7409**

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	763.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.070
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	653.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.017
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,710.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.376
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.339
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.540
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.114
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.059



**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,955.000
	0104- 10- 3	SEDIMENT BARRIER	LF	16,885.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	45.000
	0107- 1-	LITTER REMOVAL	AC	1,105.380
	0107- 2-	MOWING	AC	1,003.160
	0110- 1- 1	CLEARING & GRUBBING (43649515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43649515202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43649515203)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43649515204)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,061.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	125.000
	0120- 1-	REGULAR EXCAVATION	CY	16,887.000
	0120- 6-	EMBANKMENT	CY	8,540.000
	0160- 4-	TYPE B STABILIZATION	SY	27,445.000
	0160- 4-	TYPE B STABILIZATION	SY	5,837.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	9,877.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,587.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	7,783.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	4,800.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	533.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	3,592.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	102,354.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	25,936.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	713.300
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	387.800
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	13,565.100
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	680.600
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	5,972.800
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	247.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	17.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.100
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	7.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	7.000
	0425- 1-583	INLETS, DT BOT, TYPE H, J BOTTOM <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	5.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	9.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000

**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	16.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	244.000
	0430-174-148	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 48"SD	LF	232.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	222.000
	0430-174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	856.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	147.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	593.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	140.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,574.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	124.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	44.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	694.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/C	LF	452.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	378.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/C	LF	40.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	22.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	5.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	1.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	8.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	8.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	1.000
	0430-984-640	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 42" SD	EA	1.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	58.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	2,398.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,470.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	26.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	293.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	128.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	7,361.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	681.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	50.000
	0527- 2-	DETECTABLE WARNINGS	SF	745.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	23.100
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	48,078.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	579.000

**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	15.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	75.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	12.738
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.246
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,368.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,170.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,242.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.504
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.202
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	25.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	228.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.544
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.128
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	890.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.332
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649515202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649515203)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43649515204)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	91.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	11.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	51.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	106.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	5.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	5.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	10.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000

**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0700- 12- 50	SIGN BEACON, RELOCATE BEACON- SIGN TO REMAIN	AS	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	30.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	51.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	4,291.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43649515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43649515202)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43649515203)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43649515204)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,750.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,170.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,242.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.201
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	219.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	889.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.332
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	4,677.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	64.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	64.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	12.743
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.246
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.511
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.547
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.128
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9,348.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,353.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	134.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	115.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	2.000

**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	36,729.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	69.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	29,907.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	61.000
	0715- 4- 35	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 50' MOUNTING HEIGHT	EA	9.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	52.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	67.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	137.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,890.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,000.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	10.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	382.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	897.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	58.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	401.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	8.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	66.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	5.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 4- 6	SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, REMOVE	LF	5,612.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	3.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	100.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	10.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	20.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 3-263	CONCRETE CCTV POLE, FURNISH & INSTALL WITHOUT LOWERING DEVICE, 63'	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	29.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	7.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	16.000

**Call Order: 021 Proposal: T7410**

ALT	Item	Description	Unit	Quantity
	0649- 2-605	STEEL CCTV POLE, REMOVE POLE- COMPLETE/DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	27.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	22.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	7.000
	0660- 1-105	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 5, 2CHANNEL, SOLID STATE, SHELF MOUNTED	EA	4.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	4.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	32.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	36.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0663- 1-500	SIGNAL PRIORITY & PREEMPTION SYSTEM, ADJUST/MODIFY	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	36.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0676- 2-112	ITS CABINET, FURNISH & INSTALL, POLE MOUNT, 336S, 24" W X 46" H X 22" D	EA	1.000
	0678- 1-104	CONTROLLER ACCESSORIES, REPLACE EXISTING- FURNISH AND INSTALL, LOAD SWITCH	EA	5.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	12.000
<b>Section 0005 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	2,202.000
	1050- 42-214	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 14"	LF	672.000
	1050- 42-220	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 20"	LF	933.000
	1050- 51-208	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 8"	LF	222.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	284.000
	1050- 51-216	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 16"	LF	105.000
	1080- 26-112	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH AND INSTALL12"	EA	1.000
	1080- 27-108	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 8"	EA	2.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12"	EA	8.000
	1080- 27-116	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 16"	EA	4.000