



Bid Questions and Answers Report

Date & Time:

8/28/2019 8:36:10 AM

District Address: District 6 Construction Office, located at 1000 NW 111 Ave, Miami, FL 33172

District Phone: (305) 640-7448

Proposal: T6476

Project: 442977-1-52-01

Letting Date: 8/28/2019

Location: CENTRAL OFFICE

Description: SR 5 (US 1)

---

Question: 26871: Bid Item 0515-2-321 and Summary Sheet SQ-19 call for 54" Ped/Bicycle railing. Cover sheet calls for the Governing Standard Plans to be FY 2019-20. Index 515-062 for that year no longer has a 54" high railing, only 42" and 48".  
Please clarify.

Posted: 8/5/2019 2:41:23 PM

---

Answer: Use 54" Pedestrian / Bicycle Railing as per Standard Index 862 (2015), see attached.

Status: ANSWER PUBLISHED

Posted: 8/7/2019 11:53:03 AM

---

Document: 8982369: Index862\_2015\_Pedestrian\_Bicycle Railing\_54in.pdf

Index 862 of the Design Standards 2015.

---

Question: 27001: Section 530-4.2 requires all rubble rip rap and bedding stone be paid for by the ton, based upon truck weights, on certified scales. will truck ticket be acceptable or weigh station measurement be acceptable? Are contractors required to set up an onsite weigh station?

Posted: 8/15/2019 3:51:47 PM

---

Answer: Per Article 530-4.2 of the Standard Specifications, if the Contractor weighs trucks not in the presence of the Engineer, a certificates of weights will be required.

Status: ANSWER PUBLISHED

Posted: 8/16/2019 11:14:35 AM