



Bid Questions and Answers Report

Date & Time:

12/4/2019 8:39:24 AM

District Address: District 5 Construction Office, located at 719 South Woodland Blvd, Deland, FL 32720

District Phone: (386) 943-5350

Proposal: T5652

Project: 430975-5-52-01

Letting Date: 12/4/2019

Localtion: CENTRAL OFFICE

Description: LAKE-WEKIVA TRAIL

---

Question: 28008: FDOT has provided multiple CADD files for earthwork analysis. In order to accurately calculate the Regular Excavation and Embankment bid items, can DOT indicate which surfaces were used to calculate the 28,168 cy of Regular Excavation?

Posted: 11/8/2019 11:01:03 AM

---

Answer: Surfaces used were AMG-3SURFACEEW01, AMG-3SURFACEEW02, AMG-3SURFACEEW03, AMG-3SURFACEEW04, and AMG-3SURFACEEX. Refer to Specification 1-3 Definitions, in the Specifications Package.

Status: ANSWER PUBLISHED

Posted: 11/14/2019 1:36:26 PM

---

Question: 28039: No plan sheets are included for any work from Sta. 391+00 to the North Trailhead, including the North Trailhead. Work in this area including clearing, selective clearing, base, and drainage work is shown to be constructed and no details have been provided to determine the possible scopes of this work. Will these plans/plan sheets be provided?

Posted: 11/12/2019 9:42:59 AM

---

Answer: No, these plan sheets will not be provided. All work not shown in the plans has been included in the AMG files provided as part of the Contract Documents. Selective clearing and grubbing sheets have been provided to show the tree disposition plan for trees to remain that are within the clearing and grubbing limits.

Status: ANSWER PUBLISHED

Posted: 11/14/2019 1:38:35 PM

---

Question: 28040: No detailed plan sheets have been provided for the North Trailhead. Plan sheets and details for this area are required for review and quantification of the Base Group 6 graded aggregate area and the storm drainage work at this trail head area. Will plan sheets and details be provided for this area/work?

Posted: 11/12/2019 9:45:45 AM

---

Answer: Per the mandatory pre-bid meeting, the requested plan sheets will not be provided. All work not shown in the plans has been included in the AMG files provided as part of the Contract Documents.

Status: ANSWER PUBLISHED

Posted: 11/14/2019 1:44:26 PM

---

Question: 28041: Base Group 06 (Quantity 16,860 SY), typical sections indicate that some areas for this work are to be constructed with graded aggregate base only. Summary of Quantities plan sheet SQ-4 does not indicate the quantity of this work at any location, and detailed plan sheets for the North Trail Head area have not been provided for use in quantifying this area. Can more detailed quantity information be provided for this bid item (Base Group 06)? Can the quantity of graded aggregate base be provided? Please clarify this issue or provide additional information.

Posted: 11/12/2019 9:50:54 AM

---

Answer: See Plans Revision Number 1.

Status: ANSWER PUBLISHED

Posted: 11/19/2019 10:42:05 AM

---

Question: 28042: No earthwork cross sections have been provided for this project. This information is required to determine the methods and resources needed to perform this work, including removal of subsoil materials. Will earthwork cross sections be provided for this project?

Posted: 11/12/2019 9:53:35 AM

---

Answer: Per the mandatory pre-bid meeting, cross sections will not be provided. All work not shown in the plans has been included in the AMG files provided as part of the Contract Documents.

Status: ANSWER PUBLISHED

Posted: 11/14/2019 1:46:10 PM

---

Question: 28043: In regards to Base Group 06, where the graded aggregate base is required, we have reviewed specification Section. 204 and have noted that the material is required to have an LBR of not less than 100, is to be compacted to 100% density, and is to meet the gradations shown in Section 204-2. In review of Section 911.34 the only material that appears to meet the requirements of 204-2 is RCA base. Please confirm RCA base will be accepted for use in Base Group 06 for the graded aggregate base material on this project or clarify what other SPECIFIC material or specifications will be required or applicable for this construction.

Posted: 11/12/2019 10:50:08 AM

---

Answer: RCA base is an acceptable optional base group for the graded aggregate base material.

Status: ANSWER PUBLISHED

Posted: 11/14/2019 1:47:30 PM