



Bid Questions and Answers Report

Date & Time:

12/4/2019 8:41:47 AM

District Address: District 6 Construction Office, located at 1000 NW 111 Ave, Miami, FL 33172

District Phone: (305) 640-7448

Proposal: T6465

Project: 433455-3-52-01

Letting Date: 12/4/2019

Location: CENTRAL OFFICE

Description: SR 5 (US 1) (S. DIXIE HWY)

Question: 28088: What are the durations for the detours shown on Sheets 51 and 52 of the contract plans? Must they be picked up daily or are they allowed to remain in place until the work is complete? Posted: 11/14/2019 2:00:10 PM

Answer: All detours are designed for non-peak hours only. Peak hours are specified in Note 1 on Sheet 38. The detours must be picked up daily, and all lanes shall be open to traffic. Status: ANSWER PUBLISHED

Posted: 11/14/2019 5:30:53 PM

Question: 28147: Are there any special pigmenting requirements for the sidewalk and curb items? Posted: 11/21/2019 9:27:49 AM

Answer: The pigmenting requirements for outside curb and gutter and sidewalk items within the City of Coral Gables limits are as follows:
Colored Concrete, Federal Standard Color# 30324. Cost of colored concrete is incidental to the related bid items. Status: ANSWER PUBLISHED

Posted: 11/21/2019 5:48:35 PM