



Bid Questions and Answers Report

Date & Time: 5/22/2019 12:41:39 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4504

Project: 437838-1-52-01

Letting Date: 5/22/2019

Localtion: CENTRAL OFFICE

Description: SR 5 (US 1/FEDERAL HWY)

Question: 26065: I understand that the quantities provided on SQ-28 are for reference only, but I cannot match the quantities provided for Regular Excavation. Without having cross sections for the whole job, based on the math there is a large discrepancy with excavation for shoulder widening (should be around 1,200 CY) and the sidestreet/driveway widening (should be around 100 CY) - can you please identify how you came up with the 100.7 CY for shoulder widening and 2,326.3 for side streets/driveway widening?

Posted: 5/15/2019 3:27:37 PM

Answer: * The two earthwork quantities in question were swapped. The table should have detailed the Shoulder Widening quantity as 2,326.3 CY, and Sidestreet/Driveway Widening/Reconstruction quantity as 100.7 CY.

Status: ANSWER PUBLISHED

Posted: 5/16/2019 10:55:29 AM

* The 2,326.3 CY was inadvertently calculated based on the use of 12" stabilization. Based on our recent calculations, it should be around 1,200 CY, consistent with the question.