



Bid Questions and Answers Report

Date & Time: 5/22/2019 12:42:24 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4518  
Project: 438291-1-52-01  
Letting Date: 5/22/2019  
Location: CENTRAL OFFICE  
Description: BELLE GLADE CITYWIDE SIDEWALKS

---

Question: 25841: Can we use 100% RAP material for the stabilized subgrade? Posted: 5/2/2019 7:48:35 AM

---

Answer: No. 100 percent RAP will not be allowed on this project, plan indicates the use of 12 inch LBR 100. Status: ANSWER PUBLISHED

Posted: 5/6/2019 11:07:43 AM

---

Answer: No. Status: ANSWER VOIDED

Posted: 5/2/2019 8:25:53 AM

---

Question: 25842: May we substitute 6" of granular subbase meeting the requirements of 290-2 and 290-3 in lieu of the 12" stabilized subgrade? Posted: 5/2/2019 7:51:21 AM

---

Answer: No. The plan typical section has 12" Stabilization (LBR 100)not the normal stabilization that has a LBR of 40. Status: ANSWER PUBLISHED

Posted: 5/2/2019 8:34:32 AM

---

Question: 25850: The typical cross section calls for a 12" stabilized subgrade, but the cross section sheets show a 6" stabilization in the legend. Please confirm which is to be used. Posted: 5/2/2019 10:42:17 AM

---

Answer: 12" LBR 100 stabilized subgrade is to be used. A plan revision will be issued to show the updated legend in the Cross Section sheets. Status: ANSWER PUBLISHED

Posted: 5/6/2019 11:36:14 AM

---

Question: 25869: The summary of quantities don't appear to account for the "driveway restoration" work. Which bid item should we include this cost in? Posted: 5/3/2019 8:02:14 AM

---

Answer: All driveways to be restored with asphalt will be paid under Pay Item 334 1 12 (Superpave Asphaltic Conc., Traffic B). All driveways to be restored with concrete will be paid under Pay Item 522-2 (Concrete Sidewalk and Driveways, 6" Thick). All driveways, asphalt and concrete, will have stabilization and base included and they will be paid under Pay Items 160 -4 (Type B Stabilization) and 285-704 (Option Base Group 4) respectively. Status: ANSWER PUBLISHED  
Posted: 5/6/2019 1:46:40 PM

---

Question: 25948: The quantity of the embankment in the cross sections appear to include the stabilized subgrade and optional base course volume. Can you please verify if this is correct? Posted: 5/8/2019 4:07:52 PM

---

Answer: The contract plans will be revised to reflect the updated embankment quantity. Since the plans require the excavation to the bottom of stabilized subgrade, compensation for placing 12" stabilized LBR 100 material will be paid under Type B Stabilization pay item and under Embankment pay item. Quantity for embankment in the base areas will be to deleted. This plan revision will be issue prior to letting. Status: ANSWER PUBLISHED  
Posted: 5/9/2019 5:17:10 PM

---

Question: 25950: Selective Clearing and Grubbing, NW 2nd St Sta. 47+55.25 to 47+74.10. There is a large banyan tree that has appeared to grow around a sabal palm that is called out to be "trimmed". Over half of the trunk of the tree is located within the sidewalk footprint. Please advise. Posted: 5/9/2019 8:35:38 AM

---

Answer: The large banyan is a strangler fig. Remove the part of strangler fig that is inside the roadway R/W. Status: ANSWER PUBLISHED  
Posted: 5/15/2019 2:46:13 PM