

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190424	Call Order: 006	Proposal: T2708	District:02
Counties:	NASSAU			
Road Name:	HURRICANE IRMA (74) NASSAU DIS REC OFF STATE/ON FED SYS.			
Limits:	CR 121, OVER DEEP CREEK			
Project(s):	44216935201(*)	Federal Aid No: E172115E		
Total Roadway Length:	0.027 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	04/24/19	
Total Proposal Length:	0.027 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Acquis.	

Proposal Budget Estimate: \$374,576.00

Please read the full advertisement

Description:

The improvements under this contract consist of box culvert wingwall replacement, milling and resurfacing, base work, highway signing, guardrail, and other incidental construction on CR 121 at Bridge No. 740050 in Nassau County from MP 21.232 to MP 21.259.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: T2708

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44216935201)	LS	1.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	122.200
	0125- 3-	SELECT BEDDING MATERIAL	CY	63.900
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	22.100
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	2,521.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	254.200
	0530- 74-	BEDDING STONE	TN	90.500
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44216935201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44216935201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	960.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	480.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	660.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	257.000
	0110- 1- 1	CLEARING & GRUBBING (44216935201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	130.000
	0120- 6-	EMBANKMENT	CY	355.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	184.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	184.000
	0327- 70- 34	MILLING EXIST ASPH PAVT, 8" AVG DEPTH	SY	184.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	15.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	30.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	37.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	612.000
	0536- 73-	GUARDRAIL REMOVAL	LF	204.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,446.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	16.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44216935201)	LS	1.000