

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190424	Call Order: 001	Proposal: T2739	District:02
Counties:	LEVY			
Road Name:	C ST			
Limits:	FROM DOCK ST TO 1ST ST			
Project(s):	41142315201(*)	Federal Aid No:	00B2102B	
Project(s):	41142315601	Federal Aid No:	00B2102B	
Total Roadway Length:	0.061 Miles	Contract Days:	370	
Total Bridge Length:	0.018 Miles	Letting Date:	04/24/19	
Total Proposal Length:	0.079 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (Acq. time)	

Proposal Budget Estimate: \$5,665,355.00

Please read the full advertisement

Description:

THERE WILL BE A MANDATORY PRE-BID MEETING FOR THIS PROJECT AT 11:00 AM EST ON WEDNESDAY, MARCH 27, 2019 AT THE FLORIDA DEPARTMENT OF TRANSPORTATION, 1109 S. MARION AVE., MADISON ROOM, LAKE CITY, FL 32025. IF YOU HAVE ANY QUESTIONS CONCERNING THIS MATTER, PLEASE CONTACT JIM BROWN AT (386) 758-3798.

THIS PRE-BID MEETING IS MANDATORY BECAUSE OF THE COMPLEXITY OF THE PROJECT. ONLY PLANS AND SPECIFICATIONS WILL BE AVAILABLE PRIOR TO THE PRE-BID MEETING. THE PROSPECTIVE BIDDER SHALL BE PREQUALIFIED ACCORDING TO THE REQUIREMENTS OF FDOT RULE CHAPTER 14-22 AND SECTION 2-1 OF THE 2019 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

PROPOSALS (BIDDING DOCUMENTS) WILL BE ISSUED ONLY TO THE PROSPECTIVE BIDDERS WHO HAVE ATTENDED THE PRE-BID MEETING AND MET THE FLORIDA DEPARTMENT OF TRANSPORTATION QUALIFICATIONS FOR THIS PROJECT.

PROSPECTIVE BIDDERS ORDERING BID DOCUMENTS PRIOR TO THE PRE-BID MEETING WILL BE GIVEN ACCESS TO DOWNLOAD THE BID DOCUMENTS WITHIN 24 HOURS AFTER THE PRE-BID MEETING. THOSE PROSPECTIVE BIDDERS ORDERING THE DOCUMENTS AFTER THE PRE-BID MEETING WILL NEED TO CONTACT THE OFFICE ADVERTISING THE PROJECT TO CONFIRM ATTENDANCE AND RECEIVE ACCESS TO DOWNLOAD THE BID DOCUMENTS. PLEASE CONTACT THE OFFICE AT LEAST TWO WORKING DAYS PRIOR TO THE DEADLINE FOR OBTAINING BID DOCUMENTS TO ALLOW TIME FOR PROCESSING.

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutter, highway signing, bridges, sidewalks, sheet pile walls, modified sunshine railing, UWHC directional drill watermain, and other incidental construction on C Street from Dock Street to 1st Street in Levy County.

Call Order: 001 Proposal: T2739

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (41142315201 340014)	LS	1.000
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	232.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	129.800
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	98.800

Call Order: 001 Proposal: T2739

ALT	Item	Description	Unit	Quantity
	0400- 4- 47	CONCRETE CLASS IV, CAST IN PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	353.100
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	362.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	12.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	49,121.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	21,435.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	11,598.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	25,080.000
	0415- 2- 5	STAINLESS REINFORCING STEEL, SUBSTRUCTURE	LB	231.000
	0450- 8- 23	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 15", WIDTH 55-57"	LF	910.000
	0455- 34-314	PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, PROJECT 411423-1-1-52-01, SIZE 24"	LF	1,305.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	28,314.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	18,177.000
	0455-143- 25	TEST PILES-PRESTRESSED CONCRETE, 24" SQ W/ FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	145.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	94.000
	0515- 2-253	PEDESTRIAN/ BICYCLE RAILING, STEEL, CUSTOM PANEL, PROJECT 411423-1-52-01	LF	495.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (41142315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41142315201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (41142315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	16,110.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	655.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	238.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	238.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,836.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	4,150.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	36.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	74.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	384.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	155.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	155.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	49.000
	0104- 10- 3	SEDIMENT BARRIER	LF	279.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	653.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	62.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	1.670
	0107- 2-	MOWING	AC	1.830
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (41142315201)	LS	1.000

Call Order: 001 Proposal: T2739

ALT	Item	Description	Unit	Quantity
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (41142315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (41142315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,089.000
	0120- 1-	REGULAR EXCAVATION	CY	1,448.000
	0120- 6-	EMBANKMENT	CY	197.000
	0160- 4-	TYPE B STABILIZATION	SY	953.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	1,029.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	944.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	220.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	357.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	205.000
	0425- 1-211	INLETS, CURB, TYPE 10, <10'	EA	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	270.000
	0515- 2-313	PEDESTRIAN / BICYCLE RAILING, ALUMINUM, 42" TYPE 3	LF	22.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	50.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	156.000
	0527- 2-	DETECTABLE WARNINGS	SF	41.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,546.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.130
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	204.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	124.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.124
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	392.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41142315201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41142315201)	LS	1.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	37.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.198
Section 0004 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41142315601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (41142315601)	LS	1.000