

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190424 Call Order: 009 Proposal: T4494 District:04

Counties: PALM BEACH

Road Name: SR 80 (SOUTHERN BLVD)

Limits: AT FOREST HILL BLVD

Project(s): 43630715201(*) Federal Aid No: D418101B

Project(s): 43630715604 Federal Aid No: N/A

Total Roadway Length:	0.439 Miles	Contract Days:	410
Total Bridge Length:	0.024 Miles	Letting Date:	04/24/19
Total Proposal Length:	0.463 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$5,326,307.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, widening including bridge widening, revetment systems, bridge railing, milling and resurfacing, concrete sidewalk and driveways, concrete ditch pavement, architectural pavers, guardrail including special guardrail post for bridge mount, drainage improvements including French Drain, signing, pavement markings (paint and thermoplastic, bike lane), signalization including vehicular and pedestrian detectors, lighting, landscaping including tree relocations, irrigation, and utilities along State Road 80 (Southern Boulevard) from Crestwood/Forest Hill Boulevard, easterly 0.333 miles in Palm Beach County.

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43630715201 934213)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	58.800
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	77.100
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	150.300
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	1,459.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	2.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	9,339.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	15,866.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	14,180.000
	0450- 3- 25	PRESTRESSED SLAB UNITS, WIDTH 60", THICKNESS 15"	LF	148.000
	0450- 88- 15	PRESTRESSED SLAB UNITS TRANSVERSELY POST TENSIONED, 15"	SF	351.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	980.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE, 18" SQ	LF	175.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	429.000
	0462- 2- 11	POST TENSIONING TENDONS, SUPERSTRUCTURE STRAND WITH GROUT	LB	391.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	327.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	57.000
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	168.000
	0521- 5- 33	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F-SHAPE, PROJECT 436307-1-52-01	LF	82.000

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	74.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43630715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43630715201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43630715201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43630715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	192.000
	0102- 60-	WORK ZONE SIGN	ED	10,624.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,476.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	228.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,024.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	132.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	137.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28,748.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	110.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	85.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,381.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	410.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	410.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,308.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,142.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	28.000
	0107- 1-	LITTER REMOVAL	AC	28.540
	0107- 2-	MOWING	AC	23.540
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43630715201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43630715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43630715201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,963.000
	0120- 1-	REGULAR EXCAVATION	CY	4,329.000
	0120- 4-	SUBSOIL EXCAVATION	CY	245.000
	0120- 6-	EMBANKMENT	CY	614.000
	0160- 4-	TYPE B STABILIZATION	SY	6,587.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	5,605.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	112.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	2,287.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	28,934.000
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	1,560.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	14.800

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	765.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	677.500
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22	TN	2,432.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	33.500
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	5.000
	0425- 1-462	INLETS, CURB, TYPE J-6, >10'	EA	3.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	8.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	186.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	155.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	13.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	55.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	14.000
	0443- 70- 6	FRENCH DRAIN, 36"	LF	878.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	37.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	1,508.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,072.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	91.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	1,647.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	33.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	1,510.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,195.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	649.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	219.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	43.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	735.000
	0527- 2-	DETECTABLE WARNINGS	SF	193.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	96.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	309.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	780.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.338
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.067
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,472.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	336.000

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,318.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.292
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.486
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	37.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	131.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.071
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	44.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.073
	0999- 16-	PARTNERING, DO NOT BID (43630715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43630715201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	20.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	6.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	25.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43630715201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.066
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,390.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	62.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,386.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.414
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	58.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	44.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.008
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	11.000

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.252
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.066
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.552
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.036
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,754.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,020.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	77.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	232.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	26.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	2.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	5.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	370.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	5,559.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	7,246.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	126.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	11,250.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	15.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	18.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	4.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	15.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	4.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,980.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,239.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	20.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	358.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	174.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	686.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	6,030.000
	0633- 1-610	FIBER OPTIC CABLE, REMOVE, OVERHEAD	LF	548.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	3,794.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	264.000

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	14.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	36.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	3.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	2.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	81.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	26.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	26.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	10.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	80.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	10.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0649- 1- 17	STEEL STRAIN POLE, F&I, TYPE PS- X	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	32.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	10.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	7.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	3.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	19.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	10.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000

Call Order: 009 Proposal: T4494

ALT	Item	Description	Unit	Quantity
Section 0006 Landscape / Peripheral				
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,544.000
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (43630715201)	LS	1.000
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43630715201)	LS	1.000
	0580- 2- 8	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK SABAL PALM ONLY	EA	22.000
	0590- 1-	LANDSCAPE IRRIGATION SYSTEM	EA	1.000
Section 0007 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43630715604)	LS	1.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	1,211.000
	1050- 51-208	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 8"	LF	1,215.000
	1055- 51-108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 8"	EA	8.000
	1055- 51-408	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 8"	EA	2.000
	1080- 21-108	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 8"	EA	4.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	10.000