

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190424 Call Order: 010 Proposal: T4506 District:04
 Counties: BROWARD
 Road Name: SR 93 (I-75)
 Limits: FROM C-9 CANAL (SNAKE CREEK, MIAMI-DADE/BROWARD CO LINE) TO N OF SHERIDAN ST
 Project(s): 43783215201(*) Federal Aid No: D417006B
 Total Roadway Length: 6.000 Miles Contract Days: 252
 Total Bridge Length: 0.000 Miles Letting Date: 04/24/19
 Total Proposal Length: 6.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 30

Proposal Budget Estimate: \$10,203,838.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, milling and resurfacing including overbuild, guardrail (including removal, approach and trailing end treatment, transition, general, and double-face), crash cushion, concrete block revetment and woven filter fabric, signing and pavement markings, and traffic monitoring sites along State Road 93 (I-75) from C-9 Canal (Snake Creek, Miami-Dade/Broward County Line) for 6.00 miles to north of Sheridan Street in Broward County.

Call Order: 010 Proposal: T4506

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43783215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43783215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,110.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	660.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,422.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,228.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	130.000
	0107- 1-	LITTER REMOVAL	AC	2,605.940
	0107- 2-	MOWING	AC	1,980.820
	0110- 1- 1	CLEARING & GRUBBING (43783215201)	LS	1.000
	0120- 6-	EMBANKMENT	CY	8,933.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	66,813.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	271,377.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	4,674.600
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	8,179.600
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	22,624.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	11,083.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1,378.800
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	137.000

Call Order: 010 Proposal: T4506

ALT	Item	Description	Unit	Quantity
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	21,493.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	6,637.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	6,637.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	6.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,697.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0536- 85- 28	GUARDRAIL END TREATMENT- DOUBLE FACE TYPE II TRAILING ANCHORAGE	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	13.100
	0570- 1- 1	PERFORMANCE TURF	SY	18,114.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	22.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	22.000
	0999- 16-	PARTNERING, DO NOT BID (43783215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43783215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	64.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43783215201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.270
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	160.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	84.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.060
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	25.700
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.830
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	8.340