

**Florida Department of Transportation  
 Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190828	Call Order:	002	Proposal:	T1750	District:	01
Counties:	POLK						
Road Name:	SR 60 (HURRICANE IRMA)						
Limits:	FROM DIESEL RD TO SW 5TH AVE						
Project(s):	44385115201(*)	Federal Aid No:	E172239E				
Project(s):	44385115202	Federal Aid No:	N/A				
Total Roadway Length:	0.245 Miles	Contract Days:	165				
Total Bridge Length:	0.000 Miles	Letting Date:	08/28/19				
Total Proposal Length:	0.245 Miles	Contract Execution Days:	10				
		Special Start Date:	N/A				
		Aquis/Flexible Start Time:	60 Days (Aqui Time)				
Proposal Budget Estimate:	\$2,919,542.00						

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, drainage improvements, curb and gutter, guardrail, sheet pile wall, signing and pavement marking, and traffic signals on State Road 60 from Diesel Road, easterly approximately 0.245 miles, to SW 5th Avenue, in Polk County.

**Call Order: 002 Proposal: T1750**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44385115202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44385115202)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,685.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,272.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,145.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	165.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	296.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	509.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	165.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	165.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,102.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	264.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	72.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	21.390
	0107- 2-	MOWING	AC	16.930
	0110- 1- 1	CLEARING & GRUBBING (44385115201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	366.200
	0120- 6-	EMBANKMENT	CY	455.600
	0160- 4-	TYPE B STABILIZATION	SY	168.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	77.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,273.000

**Call Order: 002 Proposal: T1750**

ALT	Item	Description	Unit	Quantity
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	39.600
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22	TN	193.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	69.400
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	8.000
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	255.900
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	20,574.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	3.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-455	INLETS, CURB, TYPE J-5, PARTIAL	EA	1.000
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	33.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	10.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	15.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	37,242.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,205.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	28.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	17.200
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	76.500
	0530- 74-	BEDDING STONE	TN	65.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,362.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,319.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,631.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.635
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.038
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44385115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44385115202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	7.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44385115201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	54.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.028
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.042
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000

**Call Order: 002 Proposal: T1750**

ALT	Item	Description	Unit	Quantity
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.232
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.233
<b>Section 0003 Lighting</b>				
	0715- 1- 40	LIGHTING CONDUCTORS, RELOCATE EXISTING CONDUCTOR	LF	258.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	202.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	76.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000