

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190828	Call Order: 004	Proposal: T2746	District:02
Counties:	MADISON			
Road Name:	SR 6			
Limits:	FROM US 90 TO THE HAMILTON COUNTY LINE			
Project(s):	43761015201(*)	Federal Aid No:	D219018B	
Total Roadway Length:	7.952 Miles	Contract Days:	150	
Total Bridge Length:	0.101 Miles	Letting Date:	08/28/19	
Total Proposal Length:	8.053 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Acquis.	

Proposal Budget Estimate: \$4,795,482.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, highway signing, guardrail, and other incidental construction on SR 6 from US 90 to the Hamilton County line in Madison County.

**Call Order: 004 Proposal: T2746**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	78.000
	0460- 71- 1	METAL TRAFFIC RAILING, THRIE BEAM RETROFIT	LF	1,567.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43761015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43761015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,580.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	613.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	1,439.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,460.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	480.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	7,320.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,114.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	180.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	150.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	108.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	928.000
	0104- 10- 3	SEDIMENT BARRIER	LF	787.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	360.640
	0107- 2-	MOWING	AC	313.500
	0110- 1- 1	CLEARING & GRUBBING (43761015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	85.000

**Call Order: 004 Proposal: T2746**

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	5,970.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43761015201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	7,034.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	618.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	21,197.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	105,315.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	38,967.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	10,063.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	13,698.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.900
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	32.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	9.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	26.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	85.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	352.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,911.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	92,792.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	48.213
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,200.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	954.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.432
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	72.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	34.680
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,347.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	11.985
	0906-173- 21	TWO COMPONENT POLYURETHANE INJECTION, PROJECT 437610-1-52-01	LB	1,080.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43761015201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	21.471
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	17.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	24.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43761015201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	400.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	318.000

**Call Order: 004 Proposal: T2746**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.144
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	22.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	449.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	16.065
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	11.560
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.995
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.105
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.105