

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190828	Call Order: 006	Proposal: T3648	District:03
Counties:	GADSDEN			
Road Name:	CR 65A (JUNIPER CREEK RD)			
Limits:	OVER JUNIPER CREEK EXISTING BR NO. 504050			
Project(s):	43580215201(*)	Federal Aid No:	D318120B	
Total Roadway Length:	0.206 Miles	Contract Days:	180	
Total Bridge Length:	0.018 Miles	Letting Date:	08/28/19	
Total Proposal Length:	0.224 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$1,537,552.00

Please read the full advertisement

Description:

The improvements under this contract consist of replacing the existing bridge including pipes and slope protection at existing Bridge No. 504050, constructing a new bridge, Bridge No. 504156, with roadway approaches using asphalt pavement, shoulder gutter, and guardrail. Traffic will be detoured during construction and the new bridge will be constructed in one phase.

Call Order: 006 Proposal: T3648

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43580215201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	79.600
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	74.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	71.700
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	308.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	3.300
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	23,172.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,614.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	14,814.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	368.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	570.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	185.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	62.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	307.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,837.500
	0530- 74-	BEDDING STONE	TN	662.400
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	918.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	3.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43580215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43580215201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	23.500

Call Order: 006 Proposal: T3648

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	20,880.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	408.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,800.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	102.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	50.000
	0104- 10- 3	SEDIMENT BARRIER	LF	426.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	870.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,661.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (43580215201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	811.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	5,321.000
	0160- 4-	TYPE B STABILIZATION	SY	4,402.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,108.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	144.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	314.300
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	265.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	42.200
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	18.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	588.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	14.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	6.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	938.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	250.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,997.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43580215201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.389
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.389
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.058
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.058