

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT191204 Call Order: 007 Proposal: T3689 District:03  
 Counties: FRANKLIN  
 Road Name: SR 65  
 Limits: OVER GRAHAM CREEK, BR NO. 490018  
 Project(s): 21876425201(\*) Federal Aid No: D319078B  
 Total Roadway Length: 0.578 Miles Contract Days: 410  
 Total Bridge Length: 0.034 Miles Letting Date: 12/04/19  
 Total Proposal Length: 0.612 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 45 Days Other

Proposal Budget Estimate: \$3,731,040.00

Please read the full advertisement

Description: Pending Permit

The improvements under this contract consist of replacing the existing low-level bridge including piles and slope protection at existing Bridge No. 490018, SR 65 over Graham Creek in Franklin County, constructing a new bridge, Bridge No. 490036, with roadway approach reconstruction using asphalt pavement, shoulder gutter, and guardrail. An onsite diversion and temporary bridge will be utilized to maintain traffic while the existing bridge is replaced on the existing alignment.

**Call Order: 007 Proposal: T3689**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (21876425201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	227.100
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	104.700
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	110.500
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	900.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	7.500
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	52,358.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	21,474.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	20,536.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	1,075.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	1,260.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	420.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	91.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	480.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	40.700
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,216.700
	0530- 74-	BEDDING STONE	TN	789.400
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,440.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	12.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (21876425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21876425201)	LS	1.000

**Call Order: 007 Proposal: T3689**

ALT	Item	Description	Unit	Quantity
	0102- 2- 1	SPECIAL DETOUR 1 (21876425201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	31.700
	0102- 60-	WORK ZONE SIGN	ED	8,876.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,007.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	931.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	1,540.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,649.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,710.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	768.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	820.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	165.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,661.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	829.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	431.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	93.160
	0107- 2-	MOWING	AC	49.200
	0110- 1- 1	CLEARING & GRUBBING (21876425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	248.000
	0120- 1-	REGULAR EXCAVATION	CY	749.000
	0120- 4-	SUBSOIL EXCAVATION	CY	89.000
	0120- 6-	EMBANKMENT	CY	18,176.600
	0160- 4-	TYPE B STABILIZATION	SY	5,999.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,325.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,069.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	190.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	883.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,280.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	375.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	538.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.900
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	190.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	2.000
	0430-611-225	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE	EA	1.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	601.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	164.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	12.000
	0530- 74-	BEDDING STONE	TN	147.300
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	625.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000

**Call Order: 007 Proposal: T3689**

ALT	Item	Description	Unit	Quantity
	0536- 73-	GUARDRAIL REMOVAL	LF	623.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,219.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	16,484.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.584
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.590
	0751- 53- 1	BOAT RAMP- 9" PUSH SLAB, PROJECT 218764-2-52-01	SY	83.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21876425201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	0.606
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21876425201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.628
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.314
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	395.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.070
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.035