

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT191204	Call Order: 010	Proposal: T3710	District:03
Counties:	GADSDEN			
Road Name:	CR 268 (HIGH BRIDGE RD)			
Limits:	FROM JOE ADAMS RD TO BRICKYARD RD			
Project(s):	43661515201(*)	Federal Aid No: D318121B		
Total Roadway Length:	8.707 Miles	Contract Days:	450	
Total Bridge Length:	0.144 Miles	Letting Date:	12/04/19	
Total Proposal Length:	8.851 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 day Acquis.	

Proposal Budget Estimate: \$5,405,459.00

Please read the full advertisement

Description: Pending Permit

The improvements under this contract consist of adding paved shoulders, approximately 6000 linear feet of sidewalk, sheet pile walls, gravity wall, bridge railing retrofit (Bridge No. 500045), guardrail upgrades (Bridge Nos. 500072, 500099 and Bridge Culvert No. 500046), drainage improvements, intersection improvements, and other incidental construction along County Road 268 (High Bridge Road) from Joe Adams Road to Brickyard Road in Gadsden County.

Call Order: 010 Proposal: T3710

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43661515201)	LS	1.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	114.600
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	1.600
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	5.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	19,442.000
	0460- 71- 2	METAL TRAFFIC RAILING, STEEL POST AND RAIL	LF	1,013.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43661515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43661515201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43661515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	24,252.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	52,920.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	9,191.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,752.000
	0104- 10- 3	SEDIMENT BARRIER	LF	18,997.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,324.000
	0110- 1- 1	CLEARING & GRUBBING (43661515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,475.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	114.000
	0120- 1-	REGULAR EXCAVATION	CY	13,143.000
	0120- 6-	EMBANKMENT	CY	14,672.000
	0160- 4-	TYPE B STABILIZATION	SY	49,328.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	53,142.000

Call Order: 010 Proposal: T3710

ALT	Item	Description	Unit	Quantity
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	399.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,917.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	835.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	103.200
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	3,510.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	180.500
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	29.000
	0400- 4- 2	CONCRETE CLASS IV, ENDWALLS	CY	1.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	150.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	3.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	3.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	610.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	32.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	181.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	54.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	125.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	4.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	142.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	35.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	65.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	35.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	8.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	4,086.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	79.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,012.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	331.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4,740.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	363.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	3,157.000
	0527- 2-	DETECTABLE WARNINGS	SF	160.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	64.600
	0530- 74-	BEDDING STONE	TN	27.800
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	3,472.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	281.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	42.000

Call Order: 010 Proposal: T3710

ALT	Item	Description	Unit	Quantity
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	32.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	3,879.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	18.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	115.000
	0550- 60-222	FENCE GATE, TYPE B, DOUBLE, 6.1-12.0' OPENING	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	63,781.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	31,619.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	81.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	52.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	17.233
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	13.811
	0701- 18-221	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	2.681
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	4.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	26.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43661515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	536.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	340.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	168.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.288
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.205
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.049