

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT191204 Call Order: 013 Proposal: T4532 District:04
 Counties: PALM BEACH
 Road Name: CLINT MOORE RD
 Limits: FROM EL RIO TRAIL TO NW 2ND AVE
 Project(s): 43838815201(*) Federal Aid No: D419067B
 Total Roadway Length: 0.405 Miles Contract Days: 80
 Total Bridge Length: 0.000 Miles Letting Date: 12/04/19
 Total Proposal Length: 0.405 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$304,785.00

Please read the full advertisement

Description:

The improvements under this contract consist of but not limited to, sidewalk, pedestrian detectors and aluminum railing along Clint Moore Rd.

Call Order: 013 Proposal: T4532

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43838815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43838815201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43838815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,480.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	160.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	2,762.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	80.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	80.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,977.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43838815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43838815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43838815201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	695.000
	0120- 1-	REGULAR EXCAVATION	CY	626.000
	0120- 6-	EMBANKMENT	CY	62.000
	0160- 4-	TYPE B STABILIZATION	SY	2,307.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,812.000

Call Order: 013 Proposal: T4532

ALT	Item	Description	Unit	Quantity
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	24.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	138.600
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	49.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	33.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	73.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	49.000
	0527- 2-	DETECTABLE WARNINGS	SF	69.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,174.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43838815201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43838815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	154.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	26.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	122.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.011
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.010
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	54.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	92.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	146.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000