

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT191204 Call Order: 014 Proposal: T4533 District:04  
 Counties: PALM BEACH  
 Road Name: HAMLIN BLVD  
 Limits: FROM E OF 190TH ST EASTERLY TO 180TH AVE NORTH  
 Project(s): 43689915201(\*) Federal Aid No: D419056B  
 Total Roadway Length: 0.705 Miles Contract Days: 83  
 Total Bridge Length: 0.000 Miles Letting Date: 12/04/19  
 Total Proposal Length: 0.705 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$304,597.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of construction of six (6) feet asphalt sidewalk on the south side of Hamlin Blvd.

**Call Order: 014 Proposal: T4533**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43689915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43689915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	498.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,988.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	194.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,896.000
	0110- 1- 1	CLEARING & GRUBBING (43689915201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0120- 1-	REGULAR EXCAVATION	CY	640.600
	0120- 6-	EMBANKMENT	CY	801.400
	0160- 4-	TYPE B STABILIZATION	SY	4,318.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,868.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	142.100
	0527- 2-	DETECTABLE WARNINGS	SF	24.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	4.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	1,757.000
	0550- 60-223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,847.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43689915201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	49.000