

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT191204 Call Order: 002 Proposal: T5652 District:05
 Counties: LAKE, ORANGE
 Road Name: LAKE-WEKIVA TRAIL (SEGMENT 4A)
 Limits: FROM CR 435 TO SR 46
 Project(s): 43097555201(*) Federal Aid No: D519003B
 Total Roadway Length: 2.785 Miles Contract Days: 290
 Total Bridge Length: 0.000 Miles Letting Date: 12/04/19
 Total Proposal Length: 2.785 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 30 Calendar Days
 Proposal Budget Estimate: \$3,130,502.00

Please read the full advertisement

Description:

THERE WILL BE A MANDATORY PRE-BID MEETING FOR THIS PROJECT AT 10:00 AM EST ON TUESDAY, NOVEMBER 5, 2019 AT THE FLORIDA DEPARTMENT OF TRANSPORTATION, LEESBURG OPERATIONS, 1405 THOMAS AVE, LEESBURG, FL 34748. IF YOU HAVE ANY QUESTIONS CONCERNING THIS MATTER, PLEASE CONTACT STEVEN C. BUCK AT (86) 943-5171.

THIS PRE-BID MEETING IS MANDATORY BECAUSE OF THE COMPLEXITY OF THE PROJECT. ONLY PLANS AND SPECIFICATIONS WILL BE AVAILABLE PRIOR TO THE PRE-BID MEETING. THE PROSPECTIVE BIDDER SHALL BE PREQUALIFIED ACCORDING TO THE REQUIREMENTS OF FDOT RULE CHAPTER 14-22 AND SECTION 2-1 OF THE 2019 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

PROPOSALS (BIDDING DOCUMENTS) WILL BE ISSUED ONLY TO THE PROSPECTIVE BIDDERS WHO HAVE ATTENDED THE PRE-BID MEETING AND MET THE FLORIDA DEPARTMENT OF TRANSPORTATION QUALIFICATIONS FOR THIS PROJECT.

PROSPECTIVE BIDDERS ORDERING BID DOCUMENTS PRIOR TO THE PRE-BID MEETING WILL BE GIVEN ACCESS TO DOWNLOAD THE BID DOCUMENTS WITHIN 24 HOURS AFTER THE PRE-BID MEETING. THOSE PROSPECTIVE BIDDERS ORDERING THE DOCUMENTS AFTER THE PRE-BID MEETING WILL NEED TO CONTACT THE OFFICE ADVERTISING THE PROJECT TO CONFIRM ATTENDANCE AND RECEIVE ACCESS TO DOWNLOAD THE BID DOCUMENTS. PLEASE CONTACT THE OFFICE AT LEAST TWO WORKING DAYS PRIOR TO THE DEADLINE FOR OBTAINING BID DOCUMENTS TO ALLOW TIME FOR PROCESSING.

The improvements under this contract consist of construction of an asphalt trail, parking, curbed islands, drainage, roadway striping, highway signing and earthwork.

Call Order: 002 Proposal: T5652

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43097555201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43097555201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD (channelizing)	ED	178.000
	0104- 10- 3	SEDIMENT BARRIER	LF	30,768.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	585.000
	0107- 2-	MOWING	AC	13.410
	0110- 1- 1	CLEARING & GRUBBING (43097555201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.340

Call Order: 002 Proposal: T5652

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	28,168.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	635.000
	0120- 4-	SUBSOIL EXCAVATION	CY	193.000
	0120- 6-	EMBANKMENT	CY	5,625.000
	0160- 4-	TYPE B STABILIZATION	SY	58,177.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	10,497.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	13,703.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	16,860.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	3,626.700
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	3.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	353.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	37.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	231.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	19.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	2,159.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	65.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	175.000
	0527- 2-	DETECTABLE WARNINGS	SF	117.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	9.100
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	64,626.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43097555201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	35.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43097555201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	76.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	30.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	125.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	12.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	83.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	216.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	42.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.528
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.025
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.030

Call Order: 002 Proposal: T5652

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.304