

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190227	Call Order: 007	Proposal: T2729	District:02
Counties:	SUWANNEE			
Road Name:	SR 8 (I-10)			
Limits:	AT US 90 INTERCHANGE EXIT 275 AND CR 137 INTERCHANGE			
Project(s):	43499715201(*)	Federal Aid No:	D218024B	
Project(s):	43499815201	Federal Aid No:	N/A	
Total Roadway Length:	0.722 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	02/27/19	
Total Proposal Length:	0.722 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$2,272,531.00			

Please read the full advertisement

Description:

Railroad insurance is required for this Proposal at time of contract execution. Please see the Specifications Package for more information.

The improvements under this contract consist of lighting and other incidental construction on SR 8 (I-10) at US 90 Interchange Exit 275 and CR 137 Interchange, in Suwannee County.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 007 Proposal: T2729

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43499715201)	LS	1.000
	0101- 1-	MOBILIZATION (43499815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43499715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43499815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	20,370.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,290.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	21.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	21.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,660.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	589.290
	0107- 2-	MOWING	AC	532.430
	0110- 1- 1	CLEARING & GRUBBING (43499715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43499815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43499715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43499815201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	16,278.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	12,556.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	410.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	121.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	77,494.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	20,414.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	79.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 19- 13	HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120'	EA	15.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	80.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	15.000
	0715-518-150	LIGHT POLE COMP- SPECIAL DESIGN, F&I, DOUBLE ARM, POLE TOP MOUNT, ALUMINUM, 50'	EA	1.000