

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190227 Call Order: 008 Proposal: T2730 District:02
 Counties: COLUMBIA
 Road Name: SR 100
 Limits: FROM THE UNION CO LINE TO ACADEMIC AVE
 Project(s): 43429715201(*) Federal Aid No: D218022B
 Total Roadway Length: 7.350 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 02/27/19
 Total Proposal Length: 7.350 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$3,618,611.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, bridges, and other incidental construction on SR 100 from the Union County line to Academic Avenue in Columbia County.

Call Order: 008 Proposal: T2730

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	28.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43429715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43429715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,520.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,732.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	720.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	3,531.000
	0107- 1-	LITTER REMOVAL	AC	93.590
	0107- 2-	MOWING	AC	61.970
	0110- 1- 1	CLEARING & GRUBBING (43429715201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	90.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43429715201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,378.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	107,684.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	8,888.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,313.300
	0425- 82-	REPLACE GRATE	EA	8.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	32.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	2.000

Call Order: 008 Proposal: T2730

ALT	Item	Description	Unit	Quantity
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	9.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	29,939.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	43.344
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	582.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	438.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.471
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.273
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	21.795
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43429715201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	21.768
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	9.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43429715201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	194.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	146.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.157
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.448
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.091
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	7.265