

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190227 Call Order: 011 Proposal: T3688 District:03
 Counties: LEON
 Road Name: SR 63 (US 27)
 Limits: FROM CLARA KEE BLVD TO HARRIET DR
 Project(s): 44038315201(*) Federal Aid No: D318074B
 Total Roadway Length: 0.420 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 02/27/19
 Total Proposal Length: 0.420 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days Stand Acquis
 Proposal Budget Estimate: \$388,386.00

Please read the full advertisement

Description:

The improvements under this contract consist of drainage improvements, curb and gutters, traffic signals, highway signing, sidewalks/bicycle path and other incidental construction on SR 63 (US 27) Monroe Street from Clara Kee Boulevard To Harriet Drive in Leon County, Florida.

Call Order: 011 Proposal: T3688

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44038315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44038315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	32.600
	0102- 60-	WORK ZONE SIGN	ED	2,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,936.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	60.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	206.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	60.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	254.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	120.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	120.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,337.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	6.820
	0107- 2-	MOWING	AC	5.420
	0110- 1- 1	CLEARING & GRUBBING (44038315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	193.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	4.000
	0120- 1-	REGULAR EXCAVATION	CY	252.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,242.100
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT	TN	43.100
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	10.800

Call Order: 011 Proposal: T3688

ALT	Item	Description	Unit	Quantity
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	3.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	3.000
	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	38.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	92.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	186.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	35.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	4.600
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	27.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	3.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	9.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	704.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	69.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,050.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	222.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	7.000
	0527- 2-	DETECTABLE WARNINGS	SF	291.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	14.200
	0530- 74-	BEDDING STONE	TN	10.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,593.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44038315201)	LS	1.000
Section 0002 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,109.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	61.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	526.000
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	1,148.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	19.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000

Call Order: 011 Proposal: T3688

ALT	Item	Description	Unit	Quantity
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000