

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190227 Call Order: 020 Proposal: T7428 District:07
 Counties: HILLSBOROUGH
 Road Name: SR 600 (US 92)(HILLSBOROUGH AVE)
 Limits: FROM E OF N CENTRAL AVE TO W OF SR 583 (N 56TH ST)
 Project(s): 43258415201 Federal Aid No: N/A
 Project(s): 43258425201 Federal Aid No: N/A
 Project(s): 43258435201(*) Federal Aid No: D718053B
 Total Roadway Length: 3.785 Miles Contract Days: 445
 Total Bridge Length: 0.000 Miles Letting Date: 02/27/19
 Total Proposal Length: 3.785 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Calendar Days
 Proposal Budget Estimate: \$9,482,878.00

Please read the full advertisement

Description: Incentive / Disincentive

The improvements under this contract consist of milling, resurfacing, concrete rehabilitation, pavement reconstruction and widening, curb ramp and sidewalk improvements, drainage upgrades, temporary traffic control, signing and pavement markings, and traffic signal upgrades on SR 600 (US 92)(Hillsborough Ave.).

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43258415201)	LS	1.000
	0101- 1-	MOBILIZATION (43258425201)	LS	1.000
	0101- 1-	MOBILIZATION (43258435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43258415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43258425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43258435201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	107.600
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	192.000
	0102- 60-	WORK ZONE SIGN	ED	53,105.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	3,826.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	4,411.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,245.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,121.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,022.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	771.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,381.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,078.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,513.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,513.000

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	4,968.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,072.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	154.000
	0107- 1-	LITTER REMOVAL	AC	91.460
	0107- 2-	MOWING	AC	91.460
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43258415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43258415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43258415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43258425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	12,782.000
	0120- 1-	REGULAR EXCAVATION	CY	410.000
	0120- 6-	EMBANKMENT	CY	8,238.000
	0160- 4-	TYPE B STABILIZATION	SY	4,823.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	299.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	487.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	1,973.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	71,620.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,041.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,125.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	6,218.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	71.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	131,164.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	2,964.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	83,773.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	1,571.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	87.700
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	17.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	7.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	4.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	16.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	75.000
	0425- 6-	VALVE BOXES, ADJUST	EA	109.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	8.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	12.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	771.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	329.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	38.000

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	722.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	817.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	596.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	16.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	85.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	17.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	369.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	589.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,306.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,951.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	508.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	67.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	405.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4,944.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,237.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	21.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,063.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	41.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	556.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	2,714.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	579.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,362.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.608
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.488
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	9,803.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	629.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	13,991.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	17.234
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.341
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.081
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	36.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	248.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	10.142
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,129.000

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.724
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.416
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	25.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43258415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43258425201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43258435201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	83.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	32.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	9.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	91.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	20.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	10.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	8.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	25.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	10.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	9.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	46.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	3,180.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,375.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	946.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,106.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.677
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	34.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	13.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	863.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.350
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,428.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.479
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	20.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	135.000

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.057
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.359
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.298
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.187
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.179
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.784
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	5.075
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	5.075
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	396.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,878.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	6.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	66.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	8.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 4- 6	SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, REMOVE	LF	120.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	107.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	190.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	10.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	11.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 21- 9	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-50'	EA	1.000
	0649- 21- 13	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-50'	EA	1.000
	0649- 21- 19	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 70'-60'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	8.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	49.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	8.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	3.000

Call Order: 020 Proposal: T7428

ALT	Item	Description	Unit	Quantity
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	28.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	28.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	16.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	6.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	23.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	34.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	16.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	4.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	18.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	18.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	4.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	12.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	13.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	5.000