

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190227 Call Order: 021 Proposal: T7430 District:07
Counties: PASCO
Road Name: SR 35/SR 700/US 98/US 301
Limits: FROM POND AVE TO N OF LONG AVE (PIONEER MUSEUM RD)
Project(s): 42907525201(*) Federal Aid No: D718062B
Total Roadway Length: 1.103 Miles Contract Days: 160
Total Bridge Length: 0.000 Miles Letting Date: 02/27/19
Total Proposal Length: 1.103 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 90 Calendar Days

Proposal Budget Estimate: \$2,375,000.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, widening, base work, shoulder treatment, drainage improvements, curb and gutters, traffic separators, traffic signals, highway signing, sidewalks, driveways, and other incidental construction on SR 35/SR 700/US 98/US 301.

Call Order: 021 Proposal: T7430

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (42907525201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (42907525201) | LS | 1.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 136.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 25,440.000 |
| | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE | LF | 1,884.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 72,400.000 |
| | 0102- 74- 2 | CHANNELIZING DEVICE, TYPE III, 6' | ED | 160.000 |
| | 0102- 74- 7 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | LF | 1,884.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 446.000 |
| | 0102- 78- | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER | EA | 1,310.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 501.000 |
| | 0102-104- | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION | ED | 320.000 |
| | 0102-107- 1 | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION | ED | 320.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 1,417.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 38.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 28.610 |
| | 0107- 2- | MOWING | AC | 11.560 |
| | 0110- 1- 1 | CLEARING & GRUBBING (42907525201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 1,284.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 338.000 |
| | 0120- 6- | EMBANKMENT | CY | 80.000 |
| | 0285-715- | OPTIONAL BASE, BASE GROUP 15 | SY | 518.000 |
| | 0286- 2- | TURNOUT CONSTRUCTION-ASPHALT | TN | 57.200 |

Call Order: 021 Proposal: T7430

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|---|------|------------|
| | 0327- 70- 4 | MILLING EXIST ASPH PAVT, 3" AVG DEPTH | SY | 53,388.000 |
| | 0334- 1- 53 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22 | TN | 4,604.300 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22 | TN | 4,445.800 |
| | 0425- 1-351 | INLETS, CURB, TYPE P-5, <10' | EA | 1.000 |
| | 0425- 1-365 | INLETS, CURB, TYPE P-6, PARTIAL | EA | 1.000 |
| | 0425- 1-523 | INLETS, DT BOT, TYPE C, JBOT, <10' | EA | 1.000 |
| | 0425- 2- 43 | MANHOLES, P-7, PARTIAL | EA | 1.000 |
| | 0425- 5- | MANHOLE, ADJUST | EA | 1.000 |
| | 0425- 5- 1 | MANHOLE, ADJUST, UTILITIES | EA | 2.000 |
| | 0425- 11- | MODIFY EXISTING DRAINAGE STRUCTURE | EA | 2.000 |
| | 0425- 14- 1 | GRATE FOR EXISTING DRAINAGE STRUCTURE, FURNISH AND INSTALL | SF | 15.000 |
| | 0430-175-115 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD | LF | 22.000 |
| | 0430-175-136 | PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD | LF | 16.000 |
| | 0436- 1- 1 | TRENCH DRAIN, STANDARD | LF | 186.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 1,070.000 |
| | 0520- 2- 4 | CONCRETE CURB, TYPE D | LF | 660.000 |
| | 0520- 5- 41 | TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE | LF | 702.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 458.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 185.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 126.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 1,921.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 216.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 4.000 |
| | 0695- 1- 1 | TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL | EA | 8.000 |
| | 0695- 6- 12 | TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS | EA | 8.000 |
| | 0695- 7-162 | TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT | EA | 2.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 3.227 |
| | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.681 |
| | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12" | LF | 1,014.000 |
| | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18" | LF | 765.000 |
| | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" | LF | 1,088.000 |
| | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE | GM | 5.341 |
| | 0710- 11-133 | PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE, | GM | 0.198 |
| | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM | 0.038 |
| | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS | EA | 50.000 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 2.010 |

Call Order: 021 Proposal: T7430

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|---|------|-----------|
| | 0710- 11-202 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.401 |
| | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18" | LF | 929.000 |
| | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM | 0.039 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (42907525201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0639- 3- 60 | ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN | EA | 1.000 |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 31.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 11.000 |
| | 0700- 1- 50 | SINGLE POST SIGN, RELOCATE | AS | 4.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 39.000 |
| | 0700- 3-201 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF | EA | 1.000 |
| | 0700- 3-204 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF | EA | 1.000 |
| | 0700- 3-205 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF | EA | 1.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 4.000 |
| | 0700- 3-624 | SIGN PANEL, REMOVE, UP TO 50 SF WITH LIGHTING | EA | 1.000 |
| | 0700- 3-625 | SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING | EA | 1.000 |
| | 0700- 13- 15 | RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5' | EA | 3.000 |
| | 0705- 10- 1 | OBJECT MARKER, TYPE 1 | EA | 2.000 |
| | 0705- 11- 1 | DELINEATOR, FLEXIBLE TUBULAR | EA | 3.000 |
| | 0705- 11- 3 | DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN | EA | 28.000 |
| | 0710- 11-290 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE | SF | 233.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42907525201) | LS | 1.000 |
| | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND | GM | 0.134 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 1,211.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 679.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 255.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 0.866 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 9.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 44.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 1,060.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 0.435 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 1,013.000 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 23.000 |
| | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW | EA | 23.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 4.554 |
| | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" | GM | 0.566 |

Call Order: 021 Proposal: T7430

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|--|------|----------|
| | 0711- 16-131 | THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM | 1.473 |
| | 0711- 16-133 | THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP | GM | 0.083 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 1.728 |
| | 0711- 16-202 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8" | GM | 0.451 |
| | 0715- 5- 51 | LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS | EA | 2.000 |
| Section 0003 Signalization | | | | |
| | 0632- 7- 1 | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL | PI | 1.000 |
| | 0632- 7- 6 | SIGNAL CABLE, REMOVE- INTERSECTION | PI | 1.000 |
| | 0634- 4-154 | SPAN WIRE ASSEMBLY, F&I, TWO POINT, OTHER TYPE | PI | 1.000 |
| | 0634- 4-600 | SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN | PI | 1.000 |
| | 0634- 5- 1 | FIBERGLASS INSULATOR, FURNISH & INSTALL | LF | 20.000 |
| | 0650- 1- 14 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY | AS | 10.000 |
| | 0660- 2-102 | LOOP ASSEMBLY, F&I, TYPE B | AS | 4.000 |
| | 0660- 2-106 | LOOP ASSEMBLY, F&I, TYPE F | AS | 6.000 |
| | 0670- 5-400 | TRAFFIC CONTROLLER ASSEMBLY, MODIFY | AS | 1.000 |
| | 0700- 5- 22 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF | EA | 4.000 |