

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190130 Call Order: 003 Proposal: T1749 District:01

Counties: HIGHLANDS, OKEECHOBEE

Road Name: SR 70 AND POTTER RD

Limits: AT A PT E OF CR 721 AND AT POTTER RD EAST AND WEST LOCATIONS

Project(s): 44319325201 Federal Aid No: E172157E

Project(s): 44319925201 Federal Aid No: E172156E

Project(s): 44385015201(*) Federal Aid No: E172228E

Project(s): 44385015202 Federal Aid No: N/A

Total Roadway Length:	0.039 Miles	Contract Days:	110
Total Bridge Length:	0.000 Miles	Letting Date:	01/30/19
Total Proposal Length:	0.039 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$429,646.00

Please read the full advertisement

Description:

The improvements under this contract consist of Hurricane Irma Emergency Operations permanent roadway repairs, full depth reconstruction, milling and resurfacing, base work, shoulder treatment, drainage improvements, shallow subsurface polyurethane injection, resetting guardrail, and signing and pavement marking on State Road 70 east of County Road 721 in Highlands County and Potter Road East and West locations in Okeechobee County.

Call Order: 003 Proposal: T1749

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44319325201)	LS	1.000
	0101- 1-	MOBILIZATION (44319925201)	LS	1.000
	0101- 1-	MOBILIZATION (44385015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44319325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44319925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44385015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,030.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,060.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	180.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	370.000
	0104- 10- 3	SEDIMENT BARRIER	LF	220.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	153.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	10.200
	0107- 2-	MOWING	AC	10.200
	0110- 1- 1	CLEARING & GRUBBING (44319325201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44319925201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	284.000
	0120- 5-	CHANNEL EXCAVATION	CY	65.000
	0120- 6-	EMBANKMENT	CY	290.000
	0160- 4-	TYPE B STABILIZATION	SY	334.000

Call Order: 003 Proposal: T1749

ALT	Item	Description	Unit	Quantity
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	217.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	86.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	225.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	23.300
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	17.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	25.600
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	16.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	1,240.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	6.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	80.000
	0431- 1-209	PIPE LINING- HIGH DENSITY POLYETHYLENE SLIP LINER, 24", PROJECT 443850-1-52-01	LF	51.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	17.100
	0530- 3- 8	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL	CY	23.000
	0538- 1-	GUARDRAIL RESET	LF	117.000
	0570- 1- 1	PERFORMANCE TURF	SY	284.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	413.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.194
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.076
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.097
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44319325201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44319925201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44385015201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.038
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.019
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.019
	0906-173- 14	TWO COMPONENT POLYURETHANE INJECTION, PROJECT 443850-1-52-01	LB	88.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44385015201)	LS	1.000