

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190130	Call Order: 005	Proposal: T3585	District:03
Counties:	ESCAMBIA			
Road Name:	CR 168			
Limits:	OVER UNNAMED BRANCH, EXISTING BR NO. 480099			
Project(s):	43228515201(*)	Federal Aid No: D318022B		
Total Roadway Length:	0.087 Miles	Contract Days:	180	
Total Bridge Length:	0.010 Miles	Letting Date:	01/30/19	
Total Proposal Length:	0.097 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 day Acquis.	

Proposal Budget Estimate: \$1,855,923.00

Please read the full advertisement

Description:

The improvements under this contract consist of replacing a structurally deficient bridge (Bridge No. 480099) on CR 168 over Unnamed Branch northwest of Century in Escambia County, Florida. The new bridge (Bridge No. 484266) will be constructed in its existing alignment utilizing an on-site detour while the proposed structure is built. Other work included is drainage improvements and signing and pavement markings.

Call Order: 005 Proposal: T3585

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43228515201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	97.900
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	87.200
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	43.600
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	236.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	29,378.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,550.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	17,254.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	720.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE, 18" SQ	LF	285.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	74.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	230.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	18.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	852.900
	0530- 74-	BEDDING STONE	TN	303.700
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	690.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	4.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43228515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43228515201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43228515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	12.300

Call Order: 005 Proposal: T3585

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	5,415.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	100.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	338.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,935.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,005.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,022.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	374.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	210.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	14,564.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,116.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	32.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	80.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0110- 1- 1	CLEARING & GRUBBING (43228515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	536.000
	0120- 1-	REGULAR EXCAVATION	CY	2,887.600
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,078.400
	0160- 4-	TYPE B STABILIZATION	SY	1,852.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	9,739.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,478.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	90.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,921.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	102.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	277.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	26.400
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	4.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	38.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	207.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	96.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	2.000
	0430-200- 29	FLARED END SECTION, CONCRETE, 24"	EA	2.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	320.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	960.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	16.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	485.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	533.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	14,420.000

Call Order: 005 Proposal: T3585

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.920
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.996
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43228515201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.449
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.449
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.021
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.021