

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT190130	Call Order: 006	Proposal: T3695	District:03
Counties:	WALTON			
Road Name:	SR 20			
Limits:	FROM SR 81 TO CHOCTAWHATCHEE RIVER BR			
Project(s):	43775315201	Federal Aid No: N/A		
Project(s):	43775415201(*)	Federal Aid No: D318055B		
Total Roadway Length:	21.760 Miles	Contract Days:	270	
Total Bridge Length:	0.243 Miles	Letting Date:	01/30/19	
Total Proposal Length:	22.003 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 day Acquis.	
Proposal Budget Estimate:	\$11,212,437.00			

Please read the full advertisement

Description:

The improvements under this contract consist of milling/resurfacing and incidental work includes guardrail resetting, minor drainage improvements and signing and pavement marking on SR 20 from SR 81 to Choctawhatchee River Bridge. Goes with 437753-1-52-01 milling/resurfacing and incidental work includes Bridge repairs on existing Bridges No's 600101, 600102, and 600103, guardrail installation, minor drainage and signing and pavement marking on SR 81 from SR 20 to the Holmes County Line in Walton County.

Call Order: 006 Proposal: T3695

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	10.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,310.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	273.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43775315201)	LS	1.000
	0101- 1-	MOBILIZATION (43775415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43775315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43775415201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43775315201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43775315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	478.200
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	26,280.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	380.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	380.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	81,570.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	90.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	8,606.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	661.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	580.000

Call Order: 006 Proposal: T3695

ALT	Item	Description	Unit	Quantity
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	580.000
	0104- 10- 3	SEDIMENT BARRIER	LF	33,357.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	57.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	206.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	1,863.300
	0107- 2-	MOWING	AC	1,654.800
	0110- 1- 1	CLEARING & GRUBBING (43775315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43775415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	75.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	20.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	24,777.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43775315201)	LS	1.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	51,920.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	730.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	203.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	1,218.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	300,636.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	6,905.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	2,340.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	5,774.000
	0327- 70- 32	MILLING EXIST ASPH PAVT, 8 1/2" AVG DEPTH	SY	730.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	26,758.500
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	5,878.500
	0337- 7- 90	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, HIGH POLYMER	TN	23,531.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	211.700
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	6.500
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	10.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	496.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	72.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	112.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	81.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	31.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	2.000
	0431- 1-206	PIPE LINING- SPRAY APPLIED, 84" x 108" CMP ARCH, PROJECT 437754-1-52-01	LF	105.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	169.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,370.000

Call Order: 006 Proposal: T3695

ALT	Item	Description	Unit	Quantity
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	600.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL	EA	7.000
	0536- 73-	GUARDRAIL REMOVAL	LF	264.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0538- 1-	GUARDRAIL RESET	LF	2,048.000
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0570- 1- 1	PERFORMANCE TURF	SY	23,751.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	83,317.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	87.541
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	17.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	50.848
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	49.296
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43775315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43775415201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	40.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	61.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	6.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	42.330
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	9.071
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	18.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43775315201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43775415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.095
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	106.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	585.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	63.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.272
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.649
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	16.432
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	3,630.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.231

Call Order: 006 Proposal: T3695

ALT	Item	Description	Unit	Quantity
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.611