

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190130 Call Order: 007 Proposal: T4490 District:04
 Counties: BROWARD
 Road Name: NE 10TH ST, NE 5TH AVE AND SE 2ND ST
 Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS
 Project(s): 43467415201(*) Federal Aid No: D418078B
 Project(s): 43469915201 Federal Aid No: D418079B
 Total Roadway Length: 3.263 Miles Contract Days: 246
 Total Bridge Length: 0.000 Miles Letting Date: 01/30/19
 Total Proposal Length: 3.263 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15
 Proposal Budget Estimate: \$1,676,256.00

Please read the full advertisement

Description:

BROWARD MOBILITY PROJECT - POMPANO BEACH BIKE LANES

The improvements under this contract consist of sidewalk and shared use path construction and reconstruction, milling and resurfacing of existing pathways, selective clearing and grubbing including tree protection, driveway reconstruction, concrete curb, patterned pavement, pavers, detectable warnings, signing and pavement markings, and sod along NE 10th Street from NE 1st Avenue to State Road 5 (US-1/N. Federal Highway) for 1.31 miles, and additional Construction Limits along NE 5th Avenue from NE 10th Street to E. Copans Road; and along SE 2nd Street from SE 11th Avenue to State Road 5 (US-1/N. Federal Highway) for 0.59 miles, in the City of Pompano Beach, Broward County.

Call Order: 007 Proposal: T4490

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43467415201)	LS	1.000
	0101- 1-	MOBILIZATION (43469915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43467415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43469915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	12,768.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	35,962.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	360.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	174.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	844.000
	0104- 10- 3	SEDIMENT BARRIER	LF	23,650.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0110- 1- 1	CLEARING & GRUBBING (43467415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43469915201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.350
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	384.000
	0120- 1-	REGULAR EXCAVATION	CY	344.400
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,944.300
	0120- 6-	EMBANKMENT	CY	85.400
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43467415201)	LS	1.000

Call Order: 007 Proposal: T4490

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	12,826.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	10,406.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	6,003.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	11,044.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	39.500
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,582.100
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	72.000
	0520- 2-101	CONCRETE CURB, RIBBON CURB, PROJECT 434674-1-52-01	LF	5.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,704.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,246.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	31.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	46.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,356.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	25,200.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43467415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43469915201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	13.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	32.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	19.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	20.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.008
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	5.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-421	PAINTED PAVEMENT MARKINGS, STANDARD, BLUE, SOLID FOR PARKING LOT- ACCESSIBLE MARKINGS, 6"	LF	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43467415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,203.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	386.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	50.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	29.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.028
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.605
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.070
Section 0003 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000