

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190130	Call Order: 016	Proposal: T6463	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 934 (NORMANDY DR)			
Limits:	AT RUE GRANVILLE AND AT RUE VENDOME			
Project(s):	43791615201(*)	Federal Aid No:	D618039B	
Project(s):	43791615601	Federal Aid No:	N/A	
Project(s):	43791625201	Federal Aid No:	D618072B	
Project(s):	43791625601	Federal Aid No:	N/A	
Total Roadway Length:	0.199 Miles	Contract Days:	160	
Total Bridge Length:	0.000 Miles	Letting Date:	01/30/19	
Total Proposal Length:	0.199 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Calendar Days	
Proposal Budget Estimate:	\$998,368.00			

Please read the full advertisement

Description:

The improvements under this contract consist of Pedestrian Safety Improvement at SR 934 (Normandy Dr.).

Call Order: 016 Proposal: T6463

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43791615201)	LS	1.000
	0101- 1-	MOBILIZATION (43791625201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43791615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43791625201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	76.000
	0102- 60-	WORK ZONE SIGN	ED	7,360.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	600.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	132.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,880.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	440.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	154.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	228.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,044.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	160.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	160.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	3.220
	0107- 2-	MOWING	AC	0.720
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43791615201)	LS	1.000

Call Order: 016 Proposal: T6463

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43791625201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43791625201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43791615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43791625201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	716.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43791615201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43791625201)	LS	1.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	793.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	194.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	122.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	139.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	599.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	4,509.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	73.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	432.900
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,326.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	270.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	254.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	84.000
	0527- 2-	DETECTABLE WARNINGS	SF	73.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	205.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.200
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.117
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	3.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.200
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43791615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43791625201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	21.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	7.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	14.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	8.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43791615201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43791625201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	243.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	122.000

Call Order: 016 Proposal: T6463

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	132.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.097
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	168.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	295.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	503.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.297
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.066
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.139
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.098
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.104
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	504.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,896.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,470.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	2.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	6.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	6.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	17.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	490.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	21.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	210.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000

Call Order: 016 Proposal: T6463

ALT	Item	Description	Unit	Quantity
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0654- 2- 11	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC POWERED, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
Section 0005 Landscape / Peripheral				
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43791625201)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (43791625201)	LS	1.000
Section 0006 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43791615601)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43791625601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	7.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	9.000