

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190130	Call Order: 017	Proposal: T7426	District:07
Counties:	PINELLAS			
Road Name:	SR 595 (ALT US 19) (4TH AVE N)			
Limits:	FROM 5TH AVE N TO 3RD ST N			
Project(s):	43648715201(*)	Federal Aid No:	D718047B	
Total Roadway Length:	1.200 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	01/30/19	
Total Proposal Length:	1.200 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Calendar Days	

Proposal Budget Estimate: \$2,207,820.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, upgrading ADA features to conform with current standards, and general safety modifications on SR 595 (Alt. US 19) (4th Ave. N).

Call Order: 023 Proposal: T7426

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43648715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43648715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	153.000
	0102- 60-	WORK ZONE SIGN	ED	9,762.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,676.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,156.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,921.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	291.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	214.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	822.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	137.000
	0104- 10- 3	SEDIMENT BARRIER	LF	704.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	29.000
	0107- 1-	LITTER REMOVAL	AC	15.150
	0107- 2-	MOWING	AC	6.760
	0110- 1- 1	CLEARING & GRUBBING (43648715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	469.000
	0120- 1-	REGULAR EXCAVATION	CY	146.000
	0120- 6-	EMBANKMENT	CY	115.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	33,694.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,149.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	2,779.700

Call Order: 023 Proposal: T7426

ALT	Item	Description	Unit	Quantity
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	6.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	1.000
	0425- 1-205	INLETS, CURB, TYPE 9, PARTIAL	EA	1.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	244.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	57.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	435.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	106.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	68.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	391.000
	0520- 7- 1	GRANITE CURB, FURNISH & INSTALL	LF	612.000
	0520- 7- 2	GRANITE CURB, RESET	LF	1,855.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,087.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	120.000
	0527- 2-	DETECTABLE WARNINGS	SF	244.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	641.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	30.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	80.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	7.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	14.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.421
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.374
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,351.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	782.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,510.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.189
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.642
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	46.000

Call Order: 023 Proposal: T7426

ALT	Item	Description	Unit	Quantity
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.911
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.033
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	103.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	9.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	19.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	21.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43648715201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	747.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.675
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	46.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	103.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,351.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,510.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	34.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	34.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.169
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.371
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.373
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.909
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.033
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	70.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	13.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000

Call Order: 023 Proposal: T7426

ALT	Item	Description	Unit	Quantity
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	14.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	14.000