

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190731 Call Order: 003 Proposal: T1758 District:01
 Counties: POLK
 Road Name: SR 60
 Limits: FROM E OF TIGER LAKE RD TO E OF CR 630
 Project(s): 43943715201(*) Federal Aid No: D119035B
 Project(s): 43943715202 Federal Aid No: D119035B
 Total Roadway Length: 5.992 Miles Contract Days: 265
 Total Bridge Length: 0.000 Miles Letting Date: 07/31/19
 Total Proposal Length: 5.992 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days
 Proposal Budget Estimate: \$9,625,816.00

Please read the full advertisement

Description:

The improvements under this contract consist of inside turn lane widening, milling and resurfacing, base work, drainage improvements, curb and gutter, signing and pavement marking, shoulder treatment, on SR 60 from Tiger Lake Road easterly for 5.999 miles to CR 630 in Polk County Florida.

Call Order: 003 Proposal: T1758

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43943715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43943715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,576.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	21,200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	246.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,582.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	558.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,432.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	1,196.090
	0107- 2-	MOWING	AC	1,125.330
	0110- 1- 1	CLEARING & GRUBBING (43943715202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,371.000
	0120- 1-	REGULAR EXCAVATION	CY	981.000
	0120- 6-	EMBANKMENT	CY	809.000
	0160- 4-	TYPE B STABILIZATION	SY	3,184.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,611.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	204.000
	0315- 1- 5	STRESS ABSORBING MEMBRANE, PROJECT NUMBER 439437-1-52-01	SY	16,598.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	5,730.000
	0327- 70- 9	MILLING EXIST ASPH PAVT, 5 1/4" AVG DEPTH	SY	55,648.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	169,673.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	10,852.400

Call Order: 003 Proposal: T1758

ALT	Item	Description	Unit	Quantity
	0334- 1- 58	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER	TN	22,656.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	831.200
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	8,258.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	385.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	602.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	827.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	40,870.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.309
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	758.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	80.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	11.984
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	113.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	25.451
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,208.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43943715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43943715202)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	19.929
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	67.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	7.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	72.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	18.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	198.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43943715201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	672.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	119.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.155
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	11.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	110.000

Call Order: 003 Proposal: T1758

ALT	Item	Description	Unit	Quantity
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	14.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,043.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.637
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	13.390
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.257
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.367
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	12.057