

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190731 Call Order: 005 Proposal: T1763 District:01
 Counties: DESOTO
 Road Name: AMERICAN LEGION DR
 Limits: OVER PEACE RIVER, BR NO 049001
 Project(s): 44147515201(*) Federal Aid No: D119018B
 Total Roadway Length: 0.000 Miles Contract Days: 200
 Total Bridge Length: 0.035 Miles Letting Date: 07/31/19
 Total Proposal Length: 0.035 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 90 Days (Aqui Time)

Proposal Budget Estimate: \$1,437,572.00

Please read the full advertisement

Description:

The improvements under this contract consist of bridge repair and rehabilitation, sidewalk, lighting, on pedestrian bridge No. 049001 on Old State Road 70 (American Legion Drive over Peace River) in Desoto County, Florida.

Call Order: 005 Proposal: T1763

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44147515201 Bridge No. 049001)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	5.600
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	11.400
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	20,000.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	250.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	83.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	800.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	840.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44147515201)	LS	1.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	20,000.000
	0916-530- 10	REVTMENT SYSTEMS- FABRIC FORMED CONCRETE RIPRAP, PROJECT 441475-1-52-01	SY	122.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44147515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44147515201)	LS	1.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	447.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	110.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44147515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44147515201)	LS	1.000
	0110- 8- 2	UNDERWATER DEBRIS REMOVAL	LF	200.000
	0120- 6-	EMBANKMENT	CY	771.100
	0519- 78-	BOLLARDS	EA	6.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	512.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	243.500

Call Order: 005 Proposal: T1763

ALT	Item	Description	Unit	Quantity
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	336.000
	0530- 74-	BEDDING STONE	TN	86.800
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	100.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	30.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,700.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	5.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	8.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,125.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	7,400.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,850.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	10.000
	0715- 40- 2	LIGHTING FOR PEDESTRIAN BRIDGE, BARRIER WALL MOUNT FIXTURE, PROJECT 441475-1-52-01	EA	8.000