

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190731	Call Order: 007	Proposal: T1767	District:01
Counties:	MANATEE			
Road Name:	SR 64			
Limits:	AT 11TH ST W			
Project(s):	44068115201(*)	Federal Aid No: D119029B		
Project(s):	44068115202	Federal Aid No: N/A		
Total Roadway Length:	0.023 Miles	Contract Days:	80	
Total Bridge Length:	0.000 Miles	Letting Date:	07/31/19	
Total Proposal Length:	0.023 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (Aqui Time)	
Proposal Budget Estimate:	\$429,095.00			

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, curb and gutter, signalization, lighting, signing and pavement marking, sidewalks at the intersection of SR 64 and 11th Street West in Manatee County, Florida.

**Call Order: 007 Proposal: T1767**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44068115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44068115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,160.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,760.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	160.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	208.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	0.060
	0110- 1- 1	CLEARING & GRUBBING (44068115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	42.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	111.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	709.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	58.500
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	192.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	94.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	122.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	111.000
	0527- 2-	DETECTABLE WARNINGS	SF	80.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44068115201)	LS	1.000

**Call Order: 007 Proposal: T1767**

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44068115202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44068115201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	79.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	184.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	55.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.035
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.023
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.034
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.011
<b>Section 0003 Lighting</b>				
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	231.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	603.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	920.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	8.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	24.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	2.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	2.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	4.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	5.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 8	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-40'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000

**Call Order: 007 Proposal: T1767**

ALT	Item	Description	Unit	Quantity
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	6.000
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	1.000