

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: CT190731 Call Order: 008 Proposal: T1769 District:01  
Counties: LEE  
Road Name: SR 884 (COLONIAL BLVD)  
Limits: AT VARIOUS INTERSECTIONS AS LISTED IN THE PLANS  
Project(s): 44012315201(\*) Federal Aid No: D119026B  
Total Roadway Length: 3.441 Miles Contract Days: 90  
Total Bridge Length: 0.000 Miles Letting Date: 07/31/19  
Total Proposal Length: 3.441 Miles Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 120 Days (Aqui Time)  
Proposal Budget Estimate: \$372,444.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of lighting at various intersections on State Road 884 (Colonial Blvd.) from Winkler Ave easterly 3.958 miles to US 41 in Lee County.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 008 Proposal: T1769**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44012315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012315201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (44012315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,540.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,520.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	2,160.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	891.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	416.000
	0104- 10- 3	SEDIMENT BARRIER	LF	629.000
	0107- 1-	LITTER REMOVAL	AC	15.300
	0107- 2-	MOWING	AC	11.900
	0110- 1- 1	CLEARING & GRUBBING (44012315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	18.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	150.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012315201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	675.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	631.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	29.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	133.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	4,623.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	7.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	5.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	7.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	7.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	28.000