

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT190612	Call Order: 005	Proposal: T3726	District:03
Counties:	BAY			
Road Name:	SR 30 (FRONT BEACH RD)			
Limits:	FROM E LAKESHORE DR TO PORTSIDE DR			
Project(s):	43551825201(*)	Federal Aid No: D318032B		
Total Roadway Length:	1.071 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	06/12/19	
Total Proposal Length:	1.071 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Stndrd. Aquis	
Proposal Budget Estimate:	\$657,829.00			

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a Small Business as defined by FDOT. Small business size standards can be found at:
<http://www.fdot.gov/equalopportunity/bdi.shtm>

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:

<http://www.fdot.gov/contracts/forms/forms.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

Please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload tab in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at:

<http://www.fdot.gov/equalopportunity/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of construction of five foot (5') wide sidewalks with drainage improvements and various safety upgrades along both sides of S.R. 30 Front Beach Road from East Lakeshore Drive to Portside Drive in Bay County.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 005 Proposal: T3726

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43551825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43551825201 (120 DAYS))	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,496.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	156.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,398.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	19.000
	0107- 1-	LITTER REMOVAL	AC	34.740
	0107- 2-	MOWING	AC	14.540
	0110- 1- 1	CLEARING & GRUBBING (43551825201 (2.00 AC))	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	372.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	8.000
	0120- 1-	REGULAR EXCAVATION	CY	1,032.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	193.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	4,540.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	10.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	5.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	40.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	86.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	36.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	129.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	70.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	58.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	481.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	5,469.000
	0527- 2-	DETECTABLE WARNINGS	SF	579.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,577.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43551825201)	LS	1.000
Section 0002 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,117.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	64.000