

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190327 Call Order: 010 Proposal: T3713 District:03  
 Counties: LIBERTY  
 Road Name: CR 12 AND CHESTER ST  
 Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS  
 Project(s): 42985525201 Federal Aid No: D318019B  
 Project(s): 42985635201(\*) Federal Aid No: D318020B  
 Project(s): 43813415201 Federal Aid No: D318062B  
 Total Roadway Length: 2.278 Miles Contract Days: 180  
 Total Bridge Length: 0.000 Miles Letting Date: 03/27/19  
 Total Proposal Length: 2.278 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days Standard Acq  
 Proposal Budget Estimate: \$1,303,270.00

Please read the full advertisement

**Description:**

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a Small Business as defined by FDOT. Small business size standards can be found at:  
<http://www.fdot.gov/equalopportunity/bdi.shtm>

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:  
<http://www.fdot.gov/contracts/forms/forms.shtm>  
 It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

Please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload tab in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at:  
<http://www.fdot.gov/equalopportunity/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract for Financial Project ID 429855-2-52-01 consist of constructing 0.843 miles of 6' concrete sidewalk along Chester Street from SR 20 to Tom Love Road in Liberty County. This project also includes minor drainage improvements, gravity wall construction and signing. Financial Project ID 429856-3-52-01 consists of constructing 0.927 miles of 6 foot sidewalk along CR 12 from CR 12A (North Lake Mystic Road) to W.R. Tolar School in Liberty County. This project also includes minor drainage improvements and signing and pavement markings. Financial Project ID 438134-1-52-01 consists of constructing 0.505 miles of 6 foot sidewalk along CR 12 from CR 12A (South Lake Mystic Road) to CR 12A (North Lake Mystic Road) in Liberty County. This project also includes minor drainage improvements and signing and pavement markings. The summary of pay items for this project is listed in the Plans.

**Call Order: 010 Proposal: T3713**

ALT	Item	Description	Unit	Quantity
-----	------	-------------	------	----------

**Call Order: 010 Proposal: T3713**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (42985525201)	LS	1.000
	0101- 1-	MOBILIZATION (42985635201)	LS	1.000
	0101- 1-	MOBILIZATION (43813415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42985525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42985635201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43813415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	38.700
	0102- 60-	WORK ZONE SIGN	ED	10,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	45,180.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	61.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,782.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	94.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (42985525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (42985635201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43813415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	107.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	22.000
	0120- 1-	REGULAR EXCAVATION	CY	1,941.500
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,634.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	27.300
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	23,579.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	6.600
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	9.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	127.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	32.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	272.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	371.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	16.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	413.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	30.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	4.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	12.000
	0430-982-638	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 36" CD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	4.000

**Call Order: 010 Proposal: T3713**

ALT	Item	Description	Unit	Quantity
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	15.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	7.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	16.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	56.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	30.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	6,549.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,539.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	31.000
	0527- 2-	DETECTABLE WARNINGS	SF	330.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	23,579.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	13.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	13.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42985635201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43813415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	589.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	110.000