

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190327 Call Order: 013 Proposal: T4507 District:04
 Counties: BROWARD
 Road Name: SR 5 (US 1) (FEDERAL HWY)
 Limits: FROM SR 84 NORTHERLY TO SR A1A AND FROM SR 818 NORTHERLY TO SR 736
 Project(s): 43771815201(*) Federal Aid No: D418096B
 Project(s): 43771825201 Federal Aid No: D419029B
 Total Roadway Length: 3.934 Miles Contract Days: 140
 Total Bridge Length: 0.000 Miles Letting Date: 03/27/19
 Total Proposal Length: 3.934 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Calendar Days
 Proposal Budget Estimate: \$360,689.00

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a Small Business as defined by FDOT. Small business size standards can be found at:
<http://www.fdot.gov/equalopportunity/bdi.shtm>

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:
<http://www.fdot.gov/contracts/forms/forms.shtm>
 It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

Please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload tab in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at:
<http://www.fdot.gov/equalopportunity/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of but not limited to, new lighting and lighting retrofit, lighting foundations, concrete sidewalk and driveways, and signage along SR 5 (US 1) (Federal Hwy.).

Call Order: 013 Proposal: T4507

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43771815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43771815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,000.000

Call Order: 013 Proposal: T4507

ALT	Item	Description	Unit	Quantity
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	137.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0107- 1-	LITTER REMOVAL	AC	7.350
	0107- 2-	MOWING	AC	0.810
	0110- 1- 1	CLEARING & GRUBBING (43771815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	53.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	97.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	21.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43771815201)	LS	1.000
Section 0002 Lighting				
	0101- 1-	MOBILIZATION (43771825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43771825201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,280.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	420.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	52.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	560.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	308.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	60.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,150.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	21.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	10,650.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	13.000
	0715- 4- 21	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	36.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	19.000
	0715-550-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, REMOVE	EA	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43771825201)	LS	1.000