

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190327 Call Order: 001 Proposal: T5642 District:05
Counties: SEMINOLE
Road Name: SR 46
Limits: FROM ORANGE BLVD TO N OREGON ST (WEKIVA PKWY SECTION 7B)
Project(s): 24020035201(*) Federal Aid No: D518022B
Project(s): 24020035601 Federal Aid No: N/A
Total Roadway Length: 1.302 Miles Contract Days: 745
Total Bridge Length: 0.000 Miles Letting Date: 03/27/19
Total Proposal Length: 1.302 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 30 Calendar Days

Proposal Budget Estimate: \$19,124,599.00

Please read the full advertisement

Description:

The improvements under this contract consist of reconstruction, widening, milling and resurfacing, drainage improvements, curb and gutter, sidewalk, traffic signals, signing and pavement markings, lighting, intelligent transportation systems (ITS), and utility construction on SR 46.

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (24020035201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (24020035201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (24020035201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (24020035201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	28,825.000
	0102- 61-	BUSINESS SIGN	EA	9.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	12,334.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	24,278.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	189,875.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,645.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	3,020.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,644.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,528.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,000.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	15,007.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	83.000
	0107- 1-	LITTER REMOVAL	AC	515.300
	0107- 2-	MOWING	AC	429.110
	0110- 1- 1	CLEARING & GRUBBING (24020035201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,072.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	96,372.500
	0120- 4-	SUBSOIL EXCAVATION	CY	2,445.500
	0120- 6-	EMBANKMENT	CY	29,802.000
	0160- 4-	TYPE B STABILIZATION	SY	48,950.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	26,497.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	14,109.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	42,122.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	403.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	12,661.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	6,877.200
	0350- 4- 1	REINFORCED CEMENT CONCRETE PAVEMENT, 6"	SY	213.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	5.000
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	33.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	7.000
	0425- 1-431	INLETS, CURB, TYPE J-3, <10'	EA	7.000
	0425- 1-441	INLETS, CURB, TYPE J-4, <10'	EA	5.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	9.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	3.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0425- 78-	INLET CAP, PRECAST	EA	1.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	76.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	83.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	8.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	8.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	146.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	4,845.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	1,999.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	903.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,460.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	364.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	1,905.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/C	LF	478.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	220.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	2.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	8.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	350.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	5,463.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	13,376.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	687.000
	0520- 5- 16	TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	LF	2,862.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	9,719.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	693.000
	0527- 2-	DETECTABLE WARNINGS	SF	499.000
	0536- 73-	GUARDRAIL REMOVAL	LF	488.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	65,528.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	33.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	64.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	12.029
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	6,834.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	5,304.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.579
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.746
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	180.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.681
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	689.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	49.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (24020035201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	51.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	20.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	55.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	7.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	5.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	15.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	13.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	12.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	121.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (24020035201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,685.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	840.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.701
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	76.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	171.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.069
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,905.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	30.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	30.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.522
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.099
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.386
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.601
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	12,600.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,913.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	143.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	51,798.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	1,401.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	115.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	115.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3,452.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,660.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	75.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	1.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	93.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	26.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	12.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	3.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 24	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY	AS	28.000
	0650- 1- 26	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	26.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 1-103	LOOP DETECTOR INDUCTIVE, F&I, TYPE 3	EA	5.000
	0660- 1-104	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 4, 2CHANNEL, SOLID STATE, SHELF MOUNTED, TIME DELAY	EA	2.000
	0660- 1-105	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 5, 2CHANNEL, SOLID STATE, SHELF MOUNTED	EA	14.000
	0660- 1-106	LOOP DETECTOR INDUCTIVE , F&I, TYPE 6, 2 CH,SS,S,TD	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	36.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	25.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	2.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	26.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	2.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	7.000
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	1.000
Section 0005 Utilities				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	44.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	44.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (24020035601)	LS	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	275.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	47.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	7,887.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	2,886.000
	1050- 18-002	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 2- 4.9"	LF	143.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	810.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	258.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	82.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	565.000
	1050- 31-210	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	5.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	1,997.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	6,210.000
	1050- 31-220	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 20"	LF	2,945.000
	1050- 42-202	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	20.000
	1050- 42-204	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	167.000
	1050- 42-206	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	326.000
	1050- 42-210	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	160.000
	1050- 42-214	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 14"	LF	154.000
	1050- 42-216	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	84.000
	1050- 42-218	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 18"	LF	929.000
	1050- 61-120	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 20"	LF	343.000
	1055- 31-108	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 8"	EA	21.000
	1055- 31-110	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 10"	EA	2.000
	1055- 31-112	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 12"	EA	75.000
	1055- 31-116	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 16"	EA	40.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	1055- 31-120	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 20"	EA	28.000
	1055- 31-212	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, TEE, 12"	EA	5.000
	1055- 31-216	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, TEE, 16"	EA	7.000
	1055- 31-220	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, TEE, 20"	EA	3.000
	1055- 31-508	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 8"	EA	1.000
	1055- 31-512	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 12"	EA	1.000
	1055- 31-516	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 16"	EA	1.000
	1055- 51-310	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 10"	EA	2.000
	1055- 51-314	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 14"	EA	2.000
	1055- 51-316	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 16"	EA	1.000
	1055- 51-318	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 18"	EA	12.000
	1080- 21-106	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 6"	EA	73.000
	1080- 21-600	UTILITY FIXTURE, VALVE/METER BOX, REMOVE	EA	1.000
	1080- 23-102	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 2"	EA	18.000
	1080- 23-104	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 4	EA	5.000
	1080- 23-106	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 6	EA	1.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8	EA	7.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	30.000
	1080- 23-120	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 20"	EA	6.000
	1080- 23-124	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 24"	EA	1.000
	1080- 24-104	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 4"	EA	5.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	3.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	7.000
	1080- 24-110	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 10"	EA	1.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	31.000
	1080- 24-120	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 20"	EA	8.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	1.000
	1080- 25-102	UTILITY FIXTURE- BLOWOFF ASSEMBLY, FURNISH AND INSTALL, 2"	EA	3.000
	1080- 26-104	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 4"	EA	1.000
	1080- 26-106	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 6"	EA	1.000
	1080- 26-108	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 8"	EA	6.000
	1080- 26-110	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 10"	EA	1.000
	1080- 26-112	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH AND INSTALL12"	EA	6.000
	1080- 26-116	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH AND INSTALL, 16"	EA	12.000
	1080- 26-120	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 20"	EA	5.000
	1080- 27-104	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 4"	EA	4.000
	1080- 27-106	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 6"	EA	1.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	1080- 27-108	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 8"	EA	4.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12'	EA	29.000
	1080- 27-120	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 20	EA	5.000
	1080- 29-104	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 4"	EA	4.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	1.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	24.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	29.000
	1080- 29-120	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 20"	EA	5.000
	1080- 29-124	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 24"	EA	1.000
	1080- 33-104	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 4"	EA	3.000
	1080- 33-106	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 6"	EA	2.000
	1080- 33-108	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 8"	EA	3.000
	1080- 33-110	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 10"	EA	1.000
	1080- 33-112	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 12"	EA	1.000
	1080- 33-116	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 16"	EA	8.000
	1644-800-	FIRE HYDRANT, RELOCATE	EA	3.000
Section 0006 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5,463.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,353.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	1,401.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	8,675.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	50.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	9,716.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	262.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	144.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	5.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	8.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	3.000
	0633- 4- 1	SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, FURNISH & INSTALL	LF	1,599.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	687.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	21.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	3.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	293.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000

Call Order: 001 Proposal: T5642

ALT	Item	Description	Unit	Quantity
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0660- 6-421	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, CABINET EQUIPMENT	EA	2.000
	0660- 6-422	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, ABOVE GROUND EQUIPMENT	EA	2.000
	0676- 2-144	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 340, 44" W X 60" H X 25" D	EA	1.000
	0680- 1-422	SYSTEM CONTROL EQUIPMENT, RELOCATE, ADAPTIVE SIGNAL CONTROL SYSTEM- 170, CABINET EQUIPMENT	EA	2.000
	0680- 1-423	SYSTEM CONTROL EQUIPMENT, RELOCATE, ADAPTIVE SIGNAL CONTROL SYSTEM- 170, ABOVE GROUND EQUIPMENT	EA	7.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	2.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	4.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0700- 8-136	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- W/UPS, FULL COLOR, 101-200 SF	EA	1.000
	0700- 10-124	DMS SUPPORT STRUCTURE, CANTILEVER, 41-50 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000