

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT190327	Call Order: 022	Proposal: T7424	District:07
Counties:	HERNANDO			
Road Name:	CR 578 (CO LINE RD)			
Limits:	FROM SUNCOAST PKWY TO US 41 AT AYERS RD			
Project(s):	25729855201(*)	Federal Aid No:	D718040B	
Project(s):	25729855202	Federal Aid No:	D718040B	
Project(s):	25729855601	Federal Aid No:	N/A	
Total Roadway Length:	1.492 Miles	Contract Days:	860	
Total Bridge Length:	0.000 Miles	Letting Date:	03/27/19	
Total Proposal Length:	1.492 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Calendar Days	
Proposal Budget Estimate:	\$26,928,788.00			

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of the construction of four lanes of CR 578 on a new northern alignment that will tie into US 41 at Ayers Road. This project will include an 11-foot multi-use path that will connect to the Suncoast Trail and will accommodate future widening to three lanes in each direction.

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (25729855201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (25729855201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (25729855201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (25729855201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (25729855201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (25729855201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	64.000
	0102- 60-	WORK ZONE SIGN	ED	103,756.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	953.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,488.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	281,720.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	45,708.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	760.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,826.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	12.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	11,962.000
	0104- 10- 3	SEDIMENT BARRIER	LF	29,737.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	747.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	2,155.610
	0107- 2-	MOWING	AC	1,098.070
	0110- 1- 1	CLEARING & GRUBBING (25729855201)	LS	1.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.240
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	234.000
	0110- 6-	PLUGGING WATER WELLS, NON-ARTESIAN	EA	3.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	3.000
	0120- 1-	REGULAR EXCAVATION	CY	117,851.000
	0120- 4-	SUBSOIL EXCAVATION	CY	129,367.000
	0120- 6-	EMBANKMENT	CY	320,472.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	14,274.000
	0160- 4-	TYPE B STABILIZATION	SY	180,300.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	38,264.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	116,359.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,256.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	10,535.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	10,834.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	356.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	9.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	354.800
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	6.800
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	3.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	21.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	3.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	2.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	8.000
	0425- 1-472	INLETS, CURB, TYPE 7, >10'	EA	1.000
	0425- 1-473	INLETS, CURB, TYPE 7, J BOT , <10'	EA	3.000
	0425- 1-474	INLETS, CURB, TYPE 7, J BOT , >10'	EA	1.000
	0425- 1-511	INLETS, DT BOT, TYPE B, <10'	EA	14.000
	0425- 1-513	INLETS, DT BOT, TYPE B, J BOT, <10'	EA	86.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	25.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	14.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	8.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-881	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	15.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	235.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	141.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	116.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	10,810.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	4,744.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	3,162.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	3,989.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	478.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	347.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	5.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	14.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	11.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	6.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	6.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	6.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	571.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	2,991.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	17,139.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,160.000
	0520- 5- 16	TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	LF	3,285.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	183.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	242.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	8,315.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,796.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	264.000
	0527- 2-	DETECTABLE WARNINGS	SF	776.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	247.500
	0530- 74-	BEDDING STONE	TN	178.400
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	24,531.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	237.000
	0550- 60-112	FENCE GATE, TYPE A, SINGLE, 6.1-12.0' OPENING	EA	14.000
	0550- 60-123	FENCE GATE, TYPE A, DOUBLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-212	FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	409,202.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	5,449.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.015
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.515
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,312.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	320.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,042.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.284
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.096
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.183
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	23.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	68.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	19.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.745
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	677.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.187
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	550.000
	0999- 16-	PARTNERING, DO NOT BID (25729855201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25729855201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	62.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	12.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	12.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	16.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	3.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0705- 10- 4	OBJECT MARKER, TYPE 4	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	28.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	14.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	20.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	593.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (25729855201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.798
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,380.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	635.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	442.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.266
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,345.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.320
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,732.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	29.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	96.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.538
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.939
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.096
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.688
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.320
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	504.000

Section 0003 Signalization

	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	16,866.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,861.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	44.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	16,889.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	36.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	3.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	3.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	3.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	59.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE (For 17"x30")	EA	2.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	20.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	242.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	20.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	15.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	8.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	20.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	8.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	8.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	20.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	9.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,495.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	21.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	21.000
Section 0004 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25729855601)	LS	1.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	2,300.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	100.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	20.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	950.000

Call Order: 019 Proposal: T7424

ALT	Item	Description	Unit	Quantity
	1050- 51-216	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 16"	LF	14,300.000
	1055- 31-108	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 8"	EA	1.000
	1055- 31-112	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 12"	EA	13.000
	1055- 31-508	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 8"	EA	1.000
	1055- 51-116	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"	EA	78.000
	1055- 51-216	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 16"	EA	4.000
	1055- 51-316	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 16"	EA	1.000
	1055- 51-516	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 16"	EA	1.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8"	EA	1.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	2.000
	1080- 24-104	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 4"	EA	1.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	3.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	16.000
	1080- 26-116	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH AND INSTALL, 16"	EA	4.000
	1080- 29-104	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 4"	EA	4.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	4.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	66.000
	1080- 29-116	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 16"	EA	365.000
	1080- 32-112	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 12"	EA	3.000
	1080- 32-116	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 16"	EA	16.000
	1644-136- 08	FIRE HYDRANT, F&I, TRAFFIC, 3 WAY - 2 HOSE, 1PUMPER, 6"	EA	1.000
	1644-800-	FIRE HYDRANT, RELOCATE	EA	2.000