

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT190522 Call Order: 013 Proposal: T5644 District:05
 Counties: BREVARD
 Road Name: SR 500, SR 514 AND SR A1A
 Limits: INTERSECTION IMPROVEMENTS
 Project(s): 43988325201(*) Federal Aid No: D518050B
 Total Roadway Length: N/A Miles Contract Days: 60
 Total Bridge Length: N/A Miles Letting Date: 05/22/19
 Total Proposal Length: N/A Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Calendar Days

Proposal Budget Estimate: \$69,244.00

Please read the full advertisement

Description:

The improvements under this contract consist of intersection lighting retrofits and conventional light pole construction at two intersections and on SR 500. One light pole arm and luminaire is to be added to an existing light pole on SR 500 and work items include Temporary Traffic Control Items, removal of existing concrete, conduit and conductor installation, light pole complete, lighting repairs and retrofits, load center and concrete pad construction.

Call Order: 013 Proposal: T5644

ALT	Item	Description	Unit	Quantity
Section 0001 Lighting				
	0101- 1-	MOBILIZATION (43988325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43988325201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	331.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,268.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	31.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	11.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	415.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,629.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	4.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	0715- 7- 31	LOAD CENTER, RELOCATE, SECONDARY VOLTAGE	EA	1.000
	0715- 21- 2	LIGHTING REPAIRS AND RETROFITS, LED RETROFIT KIT FOR EXISTING LUMINAIRE	EA	10.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	5.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43988325201)	LS	1.000