

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT190531	Call Order: 001	Proposal: T3708	District:03
Counties:	JACKSON			
Road Name:	CR 280 (SHADY GROVE RD)			
Limits:	FROM SR 69 TO CR 286 (BLUEBERRY DR)			
Project(s):	43662015201(*)	Federal Aid No:	D318037B	
Total Roadway Length:	7.922 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	05/31/19	
Total Proposal Length:	7.922 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 day Acquis.	
Proposal Budget Estimate:	\$1,901,426.00			

Please read the full advertisement

Description:

The improvements under this contract consist of completing safety improvements consisting of widening in horizontal curves, construction of mitered end sections, placement of profiled thermoplastic pavement marking and signing along CR 280 (Shady Grove Road) from SR 69 to CR 286 (Blueberry Drive) in Jackson County, Florida.

Call Order: 001 Proposal: T3708

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43662015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43662015201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	561.000
	0102- 60-	WORK ZONE SIGN	ED	6,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,434.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	296.000
	0104- 10- 3	SEDIMENT BARRIER	LF	27,397.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0110- 1- 1	CLEARING & GRUBBING (43662015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	34.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	20.000
	0120- 1-	REGULAR EXCAVATION	CY	1,842.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	7,784.900
	0160- 4-	TYPE B STABILIZATION	SY	13,568.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	5,995.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	713.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	921.400
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	408.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	44.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	155.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	52.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	2.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	73.000
	0570- 1- 1	PERFORMANCE TURF	SY	22,827.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,917.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	8.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	101.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	18.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	15.717
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	6.564
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	4,141.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	46.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.712
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.564
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	47,942.000