

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT191030 Call Order: 009 Proposal: T4531 District:04
Counties: INDIAN RIVER, PALM BEACH
Road Name: SR 656 (17TH ST)
Limits: HURRICANE IRMA EMERGENCY OPERATIONS REPAIRS
Project(s): 44313515201(*) Federal Aid No: E172306E
Project(s): 44313515202 Federal Aid No: E172306E
Project(s): 44322315201 Federal Aid No: E172165E
Total Roadway Length: 0.000 Miles Contract Days: 285
Total Bridge Length: 1.153 Miles Letting Date: 10/30/19
Total Proposal Length: 1.153 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 60
Proposal Budget Estimate: \$972,483.00

Please read the full advertisement

Description:

The improvements under this contract consist of Hurricane Irma emergency operations repairs including but not limited to concrete traffic railing, lighting repairs, and conduit embedded concrete barriers in Indian River and Palm Beach Counties.

Call Order: 009 Proposal: T4531

| ALT | Item | Description | Unit | Quantity |
|--------------------------------|--------------|---|------|------------|
| Section 0001 Structures | | | | |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (44313515201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (44313515202) | LS | 1.000 |
| | 0400-143- | CLEANING & COATING CONCRETE SURFACE, CLASS 5 | SF | 29,437.000 |
| | 0521- 5- 41 | CONCRETE TRAFFIC RAILING- BRIDGE, 32" SHAPE, PROJECT 443135-1-52-01 | LF | 350.000 |
| | 0630- 2- 16 | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS | LF | 350.000 |
| | 0635- 3- 13 | JUNCTION BOX, FURNISH & INSTALL, EMBEDDED | EA | 35.000 |
| Section 0002 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44313515201) | LS | 1.000 |
| | 0101- 1- | MOBILIZATION (44322315201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44313515201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44313515202) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44322315201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 9,084.000 |
| | 0102- 62- | BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013 | ED | 1,710.000 |
| | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE | LF | 3,372.000 |
| | 0102- 71- 23 | TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE | LF | 3,264.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 76,860.000 |
| | 0102- 74- 7 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | LF | 36.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 616.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 718.000 |
| | 0104- 7- | SEDIMENT BASIN / CONTAINMENT SYSTEM | EA | 1.000 |
| | 0104- 9- | SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT | EA | 1.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 1,306.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 37.920 |
| | 0107- 2- | MOWING | AC | 2.740 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44313515201) | LS | 1.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44313515202) | LS | 1.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44322315201) | LS | 1.000 |
| Section 0003 Lighting | | | | |
| | 0715- 1- 12 | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6 | LF | 16,712.000 |
| | 0715- 1- 60 | LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS | LF | 16,712.000 |
| | 0715- 4- 12 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT | EA | 35.000 |
| | 0715- 4- 70 | LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION | EA | 35.000 |
| | 0715- 11-213 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP | EA | 20.000 |
| | 0715- 11-216 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP | EA | 21.000 |
| | 0715-500- 1 | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL | EA | 41.000 |
| | 0715-500- 3 | POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT | EA | 35.000 |