

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT191030 Call Order: 009 Proposal: T4531 District:04
Counties: INDIAN RIVER, PALM BEACH
Road Name: SR 656 (17TH ST)
Limits: HURRICANE IRMA EMERGENCY OPERATIONS REPAIRS
Project(s): 44313515201(*) Federal Aid No: E172306E
Project(s): 44313515202 Federal Aid No: E172306E
Project(s): 44322315201 Federal Aid No: E172165E
Total Roadway Length: 0.000 Miles Contract Days: 285
Total Bridge Length: 1.153 Miles Letting Date: 10/30/19
Total Proposal Length: 1.153 Miles Contract Execution Days: 10
Special Start Date: 05/04/20
Aquis/Flexible Start Time: N/A
Proposal Budget Estimate: \$972,483.00

Please read the full advertisement

Description:

The improvements under this contract consist of Hurricane Irma emergency operations repairs including but not limited to concrete traffic railing, lighting repairs, and conduit embedded concrete barriers in Indian River and Palm Beach Counties.

Call Order: 009 Proposal: T4531

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44313515201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44313515202)	LS	1.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	29,437.000
	0521- 5- 41	CONCRETE TRAFFIC RAILING- BRIDGE, 32" SHAPE, PROJECT 443135-1-52-01	LF	350.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	350.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	35.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44313515201)	LS	1.000
	0101- 1-	MOBILIZATION (44322315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44313515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44313515202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44322315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,084.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	1,710.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	3,372.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	3,264.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	76,860.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	36.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	616.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	718.000
	0104- 7-	SEDIMENT BASIN / CONTAINMENT SYSTEM	EA	1.000
	0104- 9-	SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1,306.000
	0107- 1-	LITTER REMOVAL	AC	37.920
	0107- 2-	MOWING	AC	2.740
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44313515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44313515202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44322315201)	LS	1.000
Section 0003 Lighting				
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	16,712.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	16,712.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	35.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	35.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	20.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	21.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	41.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	35.000