

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT190925 Call Order: 018 Proposal: T6484 District:06
Counties: MIAMI-DADE
Road Name: SR 817 AND SR 9
Limits: FROM SR 9 TO NW 199TH ST AND FROM 50TH ST TO NW 22ND AVE
Project(s): 44017415201 Federal Aid No: D619023B
Project(s): 44017515201(*) Federal Aid No: D619024B
Total Roadway Length: 10.026 Miles Contract Days: 180
Total Bridge Length: 0.000 Miles Letting Date: 09/25/19
Total Proposal Length: 10.026 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Calendar Days

Proposal Budget Estimate: \$870,207.00

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of Signalized Intersection Lighting Improvements along SR 817 and SR 9.

Call Order: 018 Proposal: T6484

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44017415201)	LS	1.000
	0101- 1-	MOBILIZATION (44017515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44017415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44017515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,605.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,045.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	670.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,396.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	440.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	496.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44017415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44017415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44017515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	492.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	62.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	436.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	75.000
	0527- 2-	DETECTABLE WARNINGS	SF	48.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	40.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44017415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44017515201)	LS	1.000

Call Order: 018 Proposal: T6484

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,526.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	70.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	26,703.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,794.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	17,341.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	3.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	5.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	7.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	10.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	2.000
	0715- 4- 42	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	99.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	16.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	59.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	6.000
Section 0004 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000