

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: CT190925      Call Order: 020      Proposal: T7425      District:07  
Counties: CITRUS, PASCO  
Road Name: US 41 (N FLORIDA AVE)  
Limits: AT E NORVELL BRYANT HWY/E PARSONS POINT RD AND VARIOUS INTERSECTION LIGHTING AS LISTED IN PLANS  
Project(s): 43982965201(\*)      Federal Aid No: D719009B  
Project(s): 43982975201      Federal Aid No: D719010B  
Total Roadway Length:      21.225 Miles      Contract Days:      185  
Total Bridge Length:      0.000 Miles      Letting Date:      09/25/19  
Total Proposal Length:      21.225 Miles      Contract Execution Days:      10  
Special Start Date:      N/A  
Aquis/Flexible Start Time:      120 Calendar Days  
Proposal Budget Estimate:      \$1,045,401.00

Please read the full advertisement

Description:

The improvements under this contract consist of intersection lighting at various locations along US 41 (N Florida Ave.).

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 020 Proposal: T7425**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43982965201)	LS	1.000
	0101- 1-	MOBILIZATION (43982975201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43982965201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43982975201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43982965201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,215.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,685.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	370.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	185.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	398.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,010.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,010.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	56.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	56.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43982965201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43982975201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,666.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,705.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	60.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	7.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	105.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	7.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	7.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	18,222.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	33.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	9.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	5.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	110.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	110.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	82.000