



Bid Questions and Answers Report

Date & Time:

4/29/2020 8:04:33 AM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4547

Project: 438387-1-52-01

Letting Date: 4/29/2020

Location: CENTRAL OFFICE

Description: VEHICLE DETECTION AT SIGNALS-TRAFFIC CONTROL DEVICES/SYSTEM

---

Question: 29511: Can the Department provide brand and model of the existing Traffic Signal Controller at each intersection? Posted: 4/17/2020 1:07:36 PM

---

Answer: The existing Traffic Signal Controller brand for all locations is Cubic/Trafficware (model NEMA 980 TS-2) Status: ANSWER PUBLISHED

Posted: 4/20/2020 9:33:16 AM

---

Question: 29554: Notes on the plans state that 'existing signal equipment to remain'. In addition, proposed new conduit is to be used only for the CCTVs and spare. Posted: 4/21/2020 4:49:17 PM

Can the Department clarify if pay item 632-7-1 New Signal Cable is to be installed in existing conduit? If so, can the Department confirm that the existing conduit is in good conditions?

---

Answer: Answer #1: The proposed new conduit is to be used for the video detection system installation and spare. Status: ANSWER PUBLISHED

Answer #2: We used pay item 632-7-1 to have signal cable installed in the proposed conduit and quantified as directed per DQE: ": For projects where you are working with the Pedestrian Signals/Detectors and/or Vehicle Detectors around an intersection, the "PI- per intersection" item should be used."

Posted: 4/21/2020 6:48:18 PM