



Bid Questions and Answers Report

Date & Time: 7/29/2020 9:21:10 AM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7434

Proposal: T2779

Project: 439490-1-52-01

Letting Date: 7/29/2020

Localtion: CENTRAL OFFICE

Description: SR 121

Question: 30596: There is a large amount of removable tape on this project. Is there is reason for that? It seems like you will pay more for the removable than you would if you use paint. Can you clarify the reasoning for this? Posted: 7/22/2020 4:06:36 PM

Answer: The use of temporary paint was considered. However, this approach is not feasible. The recommended milling depth is 1.5 inches. Traffic will be shifted from one side of the road to the other during MOT to maintain the existing number of lanes and facilitate construction. Therefore, traffic will be driving on the final friction course during MOT due to the milling depth. That is why temporary tape is called for rather than paint. Status: ANSWER PUBLISHED
Posted: 7/23/2020 3:28:12 PM